

De Jonge Excavating Contractors, Inc.

Excavation, Grading & Underground Utilities

January 10, 2022

**City of Venice
3510 Laurel Road
Venice, Fl. 34275
(941) 486-2788 (O)
Attn. Patience Anastasion**

Re: IVMF Forcemain Replacement

DeJonge's pricing for the above referenced work involves:

**Furnish & Install 550' of 4" PVC DR-18 Forcemain
Furnish & Install 10" x 4" Tapping Sleeve & Valve
Furnish & Install 4" Solid Sleeve at the Point of Connection with the Lift Station
Restore Utility Trench with Bahia Sod, Crushed Concrete Road Base, 2" of SP-12.5 Asphalt, &
6" of Fiber Reinforced Concrete
Restore Fencing Removed for Construction Activities**

Total: \$ 106,550.00

***Please see attached bid comments/clarifications regarding the proposal**

**Thanks,
Miles Hall
Project Manager/Estimator
DeJonge Excavating Contractors, Inc.
(941) 485-7799 (O)
(941) 716-2847 (M)**

De Jonge Excavating Contractors, Inc.

Excavation, Grading & Underground Utilities

Bid Comments:

1) General Conditions:

- a) City of Venice ROW use permit is not included.
- b) Density testing is included.
- c) As-builts are not included.
- d) Preconstruction video is not included.
- e) City of Venice will notify the local schools, police, fire, etc. of the construction activity.
- f) "Pricing set forth in accordance with Sarasota County Contract #176667JLS".

Restoration:

- a) Green spaces will be restored with Bahia sod.
- b) The school carpool lane will be restored with 2" of SP-12.5 Asphalt.
- c) The drive apron for the lift station/dumpster pad will be restored with 6" of fiber reinforced concrete.
- d) The PVC and chain link fence will be restored as-is.