ELEVATION- EXTERIOR- WEST

3 / AP-209 — 1/8" = 1'-0"

Grid: A — B — C — D
97'-4" / 96'-0" / 53'-0"

Labels:
- ALUMINUM COPING CAP
- MECH. SCREEN WALL
- SPANDREL GLASS
- VISION GLASS
- STOREFRONT WINDOW
- PAINTED METAL ACCENT FIN
- REVEAL
- METAL CANOPY WITH TIE-RODS
- PAINTED STUCCO
- METAL PANEL REVEAL
- METAL PANEL
- METAL CANOPY WITH TIE-RODS
- CANOPY

Levels:
- TOP OF PARAPET 47'-4"
- ROOF 43'-4"
- LEVEL 3 29'-4"
- LEVEL 2 15'-4"
- LEVEL 1 0"
- 51'-4"

Level 1 – 0' begins at the Civil Plans Finished Floor Elevation of 17.5'
BFE+2 = 16.5'

ELEVATION- EXTERIOR- EAST

4 / AP-209 — 1/8" = 1'-0"

Grid: D — C — B — A
53'-0" / 97'-4"

Labels:
- ALUMINUM COPING CAP
- PAINTED METAL ACCENT FIN
- SPANDREL GLASS
- STOREFRONT WINDOW
- VISION GLASS
- CURTAIN WALL
- REVEAL
- METAL CANOPY WITH TIE-RODS
- PAINTED STUCCO
- MECH. SCREEN WALL
- REVEAL
- PAINTED STUCCO
- METAL CANOPY WITH TIE-RODS
- CANOPY

Levels:
- TOP OF PARAPET 47'-4"
- ROOF 43'-4"
- LEVEL 3 29'-4"
- LEVEL 2 15'-4"
- LEVEL 1 0"
- 49'-4" / 51'-4"

ELEVATION- EXTERIOR- NORTH

2 / AP-209 — 1/8" = 1'-0"

Grid: 8 — 7 — 6 — 5 — 4 — 3 — 2 — 1
210'-8" / 53'-0"

Labels:
- ALUMINUM COPING CAP
- SPANDREL GLASS
- VISION GLASS
- STOREFRONT WINDOW
- PAINTED METAL ACCENT FIN
- REVEAL
- CANOPY
- PAINTED STUCCO
- MECH. SCREEN WALL
- METAL PANEL
- STOREFRONT WINDOW
- METAL TIE-ROD
- METAL DROP OFF CANOPY
- CANOPY
- SLIDING DOORS

Levels:
- TOP OF PARAPET 47'-4"
- ROOF 43'-4"
- LEVEL 3 29'-4"
- LEVEL 2 15'-4"
- LEVEL 1 0"
- 49'-4" / 51'-4"

NOTES:
- WINDOWS & DOORS - BASIS OF DESIGN TO BE INSULATED KAWNEER FRAME AND GUARDIAN CLEAR LOW E GLAZING. FRAME COLOR TO BE SELECTED FROM FULL RANGE OF STANDARD COLORS. GLASS COLOR TBD. FRAME, DOOR AND GLASS SHALL MEET FLORIDA HURRICANE DESIGN AND ENERGY REQUIREMENTS.
- PROVIDE ALLOWANCE FOR ALUMINUM PANEL SCREEN WALL ON GALVANIZED METAL FRAME FOR HVAC SCREEN (NOT SHOWN ON DRAWINGS).
- PROVIDE POWER FOR (4) SIGNAGE LOCATIONS. LOCATION TBD BY OWNER
- PROVIDE A MINIMUM OF (2) EXTERIOR STUCCO COLORS
- PROVIDE A MINIMUM OF (2) METAL PANEL COLORS
- BUILDING DESIGN, COLORS AND MATERIALS ARE SUBJECT TO CHANGE.

ELEVATION- EXTERIOR- SOUTH

1 / AP-209 — 1/8" = 1'-0"

Grid: 1 — 2 — 3 — 4 — 5 — 6 — 7 — 8
208'-0" / 53'-0" / 2'-8"

Labels:
- REVEAL
- VISION GLASS
- METAL TIE-ROD
- METAL PANEL
- STOREFRONT WINDOW
- METAL DROP OFF CANOPY
- SLIDING DOORS
- MECH. SCREEN WALL
- METAL PANEL
- SPANDREL GLASS
- VISION GLASS
- STOREFRONT WINDOW
- PAINTED METAL ACCENT FIN
- METAL PANEL
- PAINTED METAL ACCENT FIN
- CURTAIN WALL
- REVEAL
- PAINTED STUCCO

Levels:
- TOP OF PARAPET 47'-4"
- ROOF 43'-4"
- LEVEL 3 29'-4"
- LEVEL 2 15'-4"
- LEVEL 1 0"
- 51'-4"

AP-209 **BUILDING ELEVATIONS**

2023.11.30

LS3P

SIGNAGE

BUILDING RENDERING - FOR ILLUSTRATION PURPOSES ONLY

LS3P

2023.11.30

AP-210   **BUILDING RENDERING**

LS3P