Bayshore Dr. Sidewalk Update

December 11, 2024

Agenda

- Introductions
- Background
- Conceptual Design
- Objective Measures Evaluation
- Conclusion



Introductions

City Project Manager

Jon Kramer, P.E.

Assistant City Engineer

Design Engineer

Jeff Raykos, P.E.

DMK Associates, Inc.

Background

- Citizens addressed City Council and identified a safety concern with pedestrians on Bayshore Dr. They identified the area between Tarpon Street and Bayshore Circle as the most dangerous area.
- City Council directed staff to initiate a Capital Improvement Project to construct a sidewalk on one side of the road between these limits.
- Residents expressed concerns regarding which side of the road would be best for sidewalk construction.
- City staff contracted with a consulting engineering firm to prepare conceptual sidewalk designs for each side of the roadway for evaluation.

Conceptual Design

Both sides of the roadway were surveyed from front of home on the west to front of home on the east so that all existing improvements could be accurately shown.

Conceptual sidewalk designs were prepared and are available at this meeting. The design engineer is present to answer questions.

- Cost Analysis
- Connectivity
- Stormwater Design
- Utilities Project Coordination



Objective Measures Evaluation

West Side

	City of Venice - Bayshore Drive Sidew	alk - Wast Side	Ontion				
				_			
	ENGINEER'S ESTIMATE OF PROBABLE COSTS						
No. I. GENERAL	Description	Qty.	Units	Unit Price	Amt.		
101-1	Mobilization	1	LS	25,000.00	25,000.00		
1001-1	Survey, Stakeout, & Record Drawings	1	LS	20,000.00	20,000.00		
102-1	Maintenance of Traffic	1	IS.	8,000.00	8,000.00		
104-1	Erosion Control	1	LS	4,000.00	4,000.00		
2012	2.0001.001100	-		SUBTOTAL =	57,000.00		
II. CLEARING, G	RUBBING & EARTHWORK						
110-1	Clearing & Grubbing	2026	SY	3.00	6,078.00		
110-2	Mailbox (Remove, Store and Replace)	10	EA	200.00	2,000.00		
120-1	Excavation, Embankment and Grading	1	LS	15,000.00	15,000.00		
570-1	Sod (Bahia)	949	SY	5.00	4,745.00		
				SUBTOTAL =	27,823.00		
III. DRAINAGE							
425-1	Type "C" DBI	11	EA	2,000.00	22,000.00		
	Valley Gutter Inlet	4	EA	2,500.00	10,000.00		
	Mitered End Section (Elliptical)(12"x18")	1	EA	1,650.00	1,650.00		
	Elliptical Concrete Pipe Culvert (12"x18")	1033	LF	90.00	92,970.00		
	Removal of Existing Elliptical Concrete Pipe Culvert (12"x18")	398	LF	10.00	3,980.00		
	Removal of Existing Concrete Pipe Culvert (12" diameter)	49	LF	10.00	490.00		
	Removal of Existing Concrete Pipe Culvert (15" diameter)	108	LF	10.00	1,080.00		
	Removal of Exsiting Catch Basins	4	EA	500.00	2,000.00		
	Removal of Existing Catch Basin Grates/Lid and Replace with	_					
	Manhole Rim and Lid	2	EA	1,500.00	3,000.00		
					0.00		
					0.00		
				SUBTOTAL =	137,170.00		
IV. SIDEWALK	T.						
	Miami Curb	618	LF	50.00	30,900.00		
522-1	4" Concrete Sidewalk	510	SY	75.00	38,250.00		
522-2	6" Concrete Sidewalk	159	SY	138.00	21,942.00		
527-1	Detectable Warning System	20	SF	50.00	1,000.00		
				SUBTOTAL =	92,092.00		
V. DRIVEWAY							
522-3	6" Concrete Driveway & Apron	408	SY	138.00	56,304.00		
				SUBTOTAL =	56,304.00		
VI. SIGNAGE &							
700-1	Single Post Sign (Remove and Replace)	3	EA	300.00	900.00		
				SUBTOTAL =	900.00		
VII. UTILITIES	It is a set of the second						
	Remove and Reset Pole and Street Lights	3	EA	3,000.00 SUBTOTAL =	9,000.00		
SUMMARY				SUBTOTAL =	9.000.00		
I. GENERAL					\$ 57,000.00		
	RUBBING & EARTHWORK				\$ 27,823.00		
III. DRAINAGE							
IV. SIDEWALK							
V. DRIVEWAY							
VI. SIGNAGE & STRIPING							
VII. UTILITIES							
SUBTOTAL							
5% CONTINGENCY							
TOTAL =							
19118							

East Side

	ENGINEER'S ESTIMATE OF PROBABLE COSTS	- Conceptual D	esign DRA	(FT			
No.	Description	Qty.	Units	Unit Price	Amt.		
. GENERAL							
101-1	Mobilization	1	LS	25,000.00	25,00		
1001-1	Survey, Stakeout, & Record Drawings	1	LS	22,000.00	22,00		
102-1	Maintenance of Traffic	1	LS	9,000.00	9,000		
104-1	Erosion Control	1	LS	4,500.00	4,50		
				SUBTOTAL =	60,50		
	GRUBBING & EARTHWORK						
110-1	Clearing & Grubbing	2236	SY	3.00	6,70		
110-2	Mailbox (Remove, Store and Replace)	12	EA	200.00	2,40		
120-1	Excavation, Embankment and Grading	1	LS	15,000.00	15,00		
570-1	Sod (Bahia)	944	SY	5.00 SUBTOTAL =	4,72		
II. DRAINAGE				SOBIOTAL =	28,82		
425-1	Type "C" DBI	12	EA	2,000.00	24,00		
	Valley Gutter Inlet	4	EA	2,500.00	10,00		
	Mitered End Section (Elliptical)(12"x18")	1	FΔ	1,650,00	1.65		
	Elliptical Concrete Pipe Culvert (12"x18")	1206	IF.	90.00	108.54		
	Removal of Existing Elliptical Concrete Pipe Culvert (12"x18")	766	I.E.	10.00	7.66		
	Removal of Existing Concrete Pipe Culvert (12" diameter)	96	LF	10.00	96		
	Removal of Exsiting Catch Basins	5	EA	500.00	2,50		
	Exixisting Catch Basin Modification	1	EA	2,500.00	2,50		
V. SIDEWALK		<u> </u>	<u> </u>	SUBTOTAL =	157,81		
V. SIDEWALK	Miami Curb	699	I.E.	50.00	34,95		
			SY				
522-1 522-2	4" Concrete Sidewalk 6" Concrete Sidewalk	539 208	SY	75.00 138.00	40,42		
527-1	Detectable Warning System	208	SF.	50.00	1.00		
527-1	Detectable warning system	20	3F	50.00	1,000		
				SUBTOTAL =	105,079		
. DRIVEWAY							
522-3	6" Concrete Driveway & Apron	545	SY	138.00	75,210		
				SUBTOTAL =	75,210		
/I. SIGNAGE &	STRIPING						
700-1	Single Post Sign (Remove and Replace)	4	EA	300.00	1,20		
			•	SUBTOTAL =	1,20		
/II. UTILITIES							
	Remove and Reset Pole and Street Lights	3	EA	3,000.00	9,00		
	Water and Sewer Valve Adjustment	3	EA	200.00	60		
	Remove and Relocate Existing Fire Hydrant	1	EA	5,000.00	5,00		
	Remove and Relocate Utility Pole	3	EA	5,000.00	15,00		
SUMMARY		ļ		SUBTOTAL =	29,60		
I. GENERAL					\$ 60,500		
I. GENERAL II. CLEARING, GRUBBING & EARTHWORK							
III. DRAINAGE							
IV. SIDEWALK							
IV. SIDEWALK V. DRIVEWAY							
V. DRIVEWAY VI. SIGNAGE & STRIPING							
VI. UTILITIES							
SUBTOTAL							
5% CONTINGENCY							
	TOTAL =						

Cost Analysis


West Side

Total: \$399,303.45

East Side

Total: \$481,138.35

Cost Analysis



Connectivity

A sidewalk on the west side allows potential future connectivity to Bayside Dr, Baycrest Dr, and Park Ln. Dr.

THIS FORM IS INTENDED TO FACILITATE AND GUIDE THE DIALOGUE DURING A PRE-APPLICATION MEETING BY PROVIDING A PARTIAI "PROMPT LIST" OF DISCUSSION SUBJECTS. IT IS NOT A LIST OF REQUIREMENTS FOR SUBMITTAL BY THE APPLICANT.



SOUTHWEST FLORIDA WATER MANAGEMENT DISTRICT RESOURCE REGULATION DIVISION PRE-APPLICATION MEETING NOTES

FILE NUMBER:

PA 411436

Date:	5/9/2024				
Time:	14:00				
Project Name:	City of Venice - Bayshore Drive Sidewalk				
District Engineer:	Chris Kuzlo				
District ES:	Jeff Glas				
Attendees:	Kreg Maheu (kmaheu@dmkassoc.com), Tom Ballenger, Jon Kramer				
County: Sarasota		Sec/Twp/Rge:	12/39/18 and 7/39/19		
Total Land Acreage:		Project Acreage:	acres		

Prior On-Site/Off-Site Permit Activity:

N/A

Project Overview:

- The proposed activity includes the construction of a sidewalk along Bayshore Dr. between Tarpon St. and Bayshore Cir.
- The proposed activity may qualify for an exemption as long as criteria listed under 62-330.051(4) are met

Environmental Discussion: (Wetlands On-Site, Wetlands on Adjacent Properties, Delineation, T&E species, Easements, Drawdown Issues, Setbacks, Justification, Elimination/Reduction, Permanent/Temporary Impacts, Secondary and Cumulative Impacts, Mitigation Options, SHWL, Upland Habitats, Site Visit, etc.)

A site visit by District staff will be required to verify the presence or absence of wetlands and/or surface
waters. Prior to the site visit, District staff will contact the applicant or authorized agent to provide an
approximate date of the site visit and to ensure that the project area is accessible. If wetlands or surface
waters are discovered during the site visit, additional information may be required. A site visit will not be
scheduled until the appropriate signatures on the application and the fee is submitted.

Site Information Discussion: (SHW Levels, Floodplain, Tailwater Conditions, Adjacent Off-Site Contributing Sources, Receiving Waterbody, etc.)

- Existing roadway/intersections along Bayshore Dr. from Tarpon St. to Bayshore Cir.
- Watersheds Island of Venice. 100-year riverine floodplain along the project area. Watershed model information is available for download using the following link: https://watermatters.sharefile.com/d-s8c9019e00fd243908654e733a6b2016c
- WBIDs Roberts Bay (WBID 2018A). WBID is currently listed for nutrient related impairments. WBIDs need to be independently verified by the consultant
- Sarasota Bay Estuarine System is OFW.
- Check FDEP MapDirect layer for possible contamination points within/adjacent to the project area. <u>FDEP Map Direct</u>

Please verify with FDEP if any have current contamination issues after the application is submitted. For known contamination within the site or within 100' beyond the proposed stormwater management system:

- After the application is submitted, please contact FDEP staff listed below and provide them with the ERP Application ID # along with a mounding analysis (groundwater elevation versus distance) of the proposed stormwater management system that shows the proposed groundwater mound will not adversely impact the contaminated area. FDEP will review the plans submitted to the District and mounding analysis to determine any adverse impacts. Provide documentation from FDEP that the proposed construction will not result in adverse impacts. This is required prior to the ERP Application being deemed complete.
- FDEP Contacts:
- For projects located within Sarasota, DeSoto, Highlands and Charlotte Counties: Phil Wilkerson; Philip.wilkerson@floridadep.gov
- Any wells on site should be identified and their future use/abandonment must be designated.

Stormwater Design

A pre-application meeting was held with the Southwest Florida Water Management District (SWFWMD) to review the proposed stormwater design for both sides.

Construction of a sidewalk on the west side allows more runoff to be collected in the proposed stormwater management system.



Utilities Project Coordination

Adopted Water Main Replacement Phase 7 project will abandon water lines and meters behind homes on the west side and install new water lines and meters in the right-of-way in front of the homes.

Construction of a sidewalk on the west side will allow the utility lines to be constructed simultaneously.

Conclusion

Staff will proceed with the final design and construction of a sidewalk along the west side of the road.



Thank you

Jon Kramer, P.E.
Assistant City Engineer
941-882-7410
jkramer@venicefl.gov