






**MEMORANDUM  
FINANCE DEPARTMENT**

---

**TO:** Ed Lavallee, City Manager   
**THRU:** Linda Senne, Finance Director   
**FROM:** Peter Boers, Procurement Manager   
**DATE:** April 13, 2018  
**MEETING DATE:** April 24, 2018  
**SUBJECT:** Approval of Ranking for RFQ 3079-18 Construction Management at Risk Services for the City of Venice Public Safety Facility

---

**Background:**

Request for Qualifications (RFQ) 3079-18 for Construction Management at Risk Services for the City of Venice Public Safety Facility was distributed on January 27, 2018; eight (8) proposals were received on March 2, 2018. On March 15, 2018, an evaluation committee met to review, discuss, and score the proposals received. The eight (8) proposals were ranked in the following order and the top three (3) firms were invited in for interviews/presentations on April 4, 2018.

Rank	Proposer	Sum of Rankings
1	Ajax/Tandem Construction (a Joint Venture)	5
2	Gilbane Building Company	9
3	Willis Smith Construction, Inc.	11
4	A2 Group, Inc.	16
5	Gates Butz Institutional Construction, LLC	19
6	Wharton-Smith, Inc.	21
7	Burke Construction Group, Inc.	27
8	Chris-Tel Construction	32

On April 4, 2018, the evaluation committee met again to hear oral presentations and conduct interviews with the top three (3) shortlisted proposers. The proposer's were ranked in the following order:

Rank	Firm	Sum of Ranks
1	Ajax/Tandem Construction (a Joint Venture)	5
2	Gilbane Building Company	8
3	Willis Smith Construction, Inc.	11

On April 5, 2018, a crane fell at the construction site of the new police headquarters in St. Petersburg, Florida. Several construction workers were present, but no one was hurt. This was on the jobsite of the top ranked proposer, Ajax Building Corporation.

The Evaluation committee, along with the City's Owners Representative met once again to discuss the incident with the Presidents of Ajax Building Corporation and Tandem Construction. A summary of those discussions and the findings is attached for information.

Based upon the final scores and ranking, the evaluation committee recommends authorization for staff to negotiate an agreement with the top ranked proposer,

In the event that the City is unable to come to terms with the top ranked proposer, staff will end negotiations with that firm and begin negotiations with the next ranked firm until a suitable agreement can be reached.

**Requested Action:**

Approval of the ranking of proposers for RFQ 3079-18 for Construction Management at Risk Services for the City of Venice Public Safety Facility and authorize staff to begin negotiations with the top ranked firm.

**City Attorney Review:**

Not Applicable at this time.

**Risk Management Review:**

Not Applicable at this time.

**Request for Qualifications 3079-18  
Summary Score Sheet**

	<b>Evaluator 1 Score</b>	<b>Rank Evaluator 1</b>	<b>Evaluator 2 Score</b>	<b>Rank Evaluator 2</b>	<b>Evaluator 3 Score</b>	<b>Rank Evaluator 3</b>	<b>Evaluator 4 Score</b>	<b>Rank Evaluator 4</b>	<b>Total of Rankings Evaluator</b>	<b>Rank</b>
<b>A2 Group, Inc.</b>	65	4	55	6	79	3	75	3	16	4
<b>Ajax/Tandem Construction (a Joint Venture)</b>	90	1	83	2	88	1	100	1	5	1
<b>Burke Construction Group, Inc.</b>	50	7	40	7	67	6	44	7	27	7
<b>Chris-Tel Construction</b>	40	8	35	8	55	8	36	8	32	8
<b>Gates Butz Institutional Construction LLC</b>	60	5	65	5	77	4	50	5	19	5
<b>Gilbane Building Company</b>	85	2	90	1	77	4	90	2	9	2
<b>Wharton-Smith, Inc.</b>	55	6	70	3	67	6	46	6	21	6
<b>Willis A. Smith Construction, Inc.</b>	85	2	67	4	83	2	75	3	11	3



**CITY OF VENICE**  
401 W. Venice Avenue Venice, FL. 34285  
**NOTICE OF ACTION**

**REQUEST FOR QUALIFICATIONS (RFQ) # 3079-18**

**RFQ TITLE:** Construction Management at Risk Services for City of Venice  
Public Safety Facility

**SUBMITTAL DEADLINE:** March 2, 2018

**SUBJECT:** Notice of Shortlist

Based on Evaluation Committee's review of proposals on March 15, 2018. The City of Venice (City) has ranked proposers responding to the above referenced RFQ as follows:

Rank	Proposer	Total of Rankings
<b>1</b>	<b>Ajax/Tandem Construction (a Joint Venture)</b>	<b>5</b>
<b>2</b>	<b>Gilbane Building Company</b>	<b>9</b>
<b>3</b>	<b>Willis Smith Construction, Inc.</b>	<b>11</b>
4	A2 Group, Inc.	16
5	Gates Butz Institutional Construction, LLC	19
6	Wharton-Smith, Inc.	21
7	Burke Construction Group, Inc.	27
8	Chris-Tel Construction	32

The top three (3) ranked firms (**in bold font above**) will be invited for presentations and interviews as the next step in the process.

By:   
Peter A. Boers, Procurement Manager

Date: 03/16/2018



**Request for Qualifications 3079-18**  
**Summary Ranking from Presentations / Interviews**

	Rank Evaluator 1	Rank Evaluator 2	Rank Evaluator 3	Rank Evaluator 4	Total of Rankings Evaluator	Rank
<b>Ajax/Tandem Construction (a Joint Venture)</b>	1	2	1	1	5	1
<b>Gilbane Building Company</b>	3	1	2	2	8	2
<b>Willis A. Smith Construction, Inc.</b>	2	3	3	3	11	3



**CITY OF VENICE**  
401 W. Venice Avenue Venice, FL. 34285

## NOTICE OF ACTION

**REQUEST FOR QUALIFICATIONS (RFQ) # 3079-18**

**RFQ TITLE:** Construction Management at Risk Services for City of Venice  
Public Safety Facility


**SUBMITTAL DEADLINE:** March 2, 2018

**SUBJECT:** NOTICE OF RECOMMENDED AWARD

Based on Evaluation Committee's ranking of proposals on April 4, 2018. The City of Venice (City) has ranked proposers responding to the above referenced RFQ as follows:

Firm	Sum of Ranks	Rank
<b>Ajax/Tandem Construction (a Joint Venture)</b>	<b>5</b>	<b>1</b>
Gilbane Building Company	8	2
Willis Smith Construction, Inc.	11	3

It is the City's intent to initiate contract negotiations with the top ranked firm (**in bold font above**).

By:   
Peter A. Boers, Procurement Manager

Date: 04/05/2018

## Peter Boers

---

**From:** Ron Ford <[rford@otbconsultinginc.com](mailto:rford@otbconsultinginc.com)>  
**Sent:** Monday, April 16, 2018 2:48 PM  
**To:** Robert W. Goodson; Peter Boers; Lenox E. Bramble; Tom Mattmuller; Kathleen Weeden  
**Cc:** Foard Meriwether  
**Subject:** RE: Conversation with Ajax RE: St. Pete Project Event

All-

As requested, we did a brief review of the report provided by Ajax on the recent crane collapse at the St. Pete project. According to the information provided it appears the cause was operator error-the load lifted exceeded the maximum load for the crane as configured (Lift Detail Summary/Findings on page 3). Note, we understand there is an ongoing investigation by OSHA. Those results should be provided to the City of Venice when available.

The erection subcontractor-Quinlan Enterprises, a third tier sub to the steel subcontractor-Trinity Fabricators, owned the crane and was operating it at the time of the collapse. Proper documentation had been provided for the crane operator, and equipment inspections were completed prior to start of work. The report documents violations committed by Quinlan during their time on the project, including notices issued, ending with their termination. They were in the process of demobilizing when the accident occurred.

From the report, there were no injuries or damage to constructed completed and in place. Additional measures have been implemented by Ajax to enhance vetting of lower tier subcontractors.

Please let me know if you have any questions.

**Ron Ford**  
[rford@otbconsultinginc.com](mailto:rford@otbconsultinginc.com)  
813.205.9774

**Otb Consulting, Inc.**  
305 South MacDill Avenue  
Tampa, FL 33609  
[www.otbconsultinginc.com](http://www.otbconsultinginc.com)

**NOTICE: PRIVILEGED AND CONFIDENTIAL ATTORNEY WORK PRODUCT:**

This e-mail message is intended only for the personal use of the recipient(s) named above. This message may be an attorney-client communication and as such privileged and confidential. If you are not an intended recipient, you may not review, copy or distribute this message. If you have received this communication in error, please notify us immediately by e-mail and delete the original message and any attachments.

---

**From:** Marc Reeves [<mailto:Marc@ajaxbuilding.com>]  
**Sent:** Monday, April 16, 2018 9:49 AM  
**To:** Ron Ford; Bill Byrne; Rob Goodson; Peter Boers; Lenox E. Bramble; Tom Mattmuller; Kathleen Weeden  
**Subject:** RE: Conversation with Ajax RE: St. Pete Project Event

All,

Thank you for the opportunity to speak with you last week concerning the incident on 4/5/18 at the St. Petersburg Police Facility project. I have completed the Ajax incident investigation report and, as per your request, am providing the report to you. Should you have any questions, please feel free to contact me.

Thank you,  
*Marc Reeves*, CRIS  
Director of Risk Management



1080 Commerce Blvd.  
Midway, Fl. 32343  
Phone: 850-224-9571  
Fax: 850-224-2496

---

**From:** Ron Ford [mailto:[rford@otbconsultinginc.com](mailto:rford@otbconsultinginc.com)]

**Sent:** Thursday, April 12, 2018 4:34 PM

**To:** Bill Byrne <[Bill@ajaxbuilding.com](mailto:Bill@ajaxbuilding.com)>; Marc Reeves <[Marc@ajaxbuilding.com](mailto:Marc@ajaxbuilding.com)>; Rob Goodson <[rgoodson@venicegov.com](mailto:rgoodson@venicegov.com)>; Peter Boers <[PBoers@Venicegov.com](mailto:PBoers@Venicegov.com)>; Lenox E. Bramble <[LBramble@Venicegov.com](mailto:LBramble@Venicegov.com)>; Tom Mattmuller <[TMattmuller@Venicegov.com](mailto:TMattmuller@Venicegov.com)>; Kathleen Weeden <[KWeeden@Venicegov.com](mailto:KWeeden@Venicegov.com)>

**Subject:** Conversation with Ajax RE: St. Pete Project Event

All

Marc Reeves-Rick Manager for Ajax and I had a follow up discussion this afternoon concerning the event that occurred at Ajax's St. Pete project last week. They are preparing a formal document to provide the City, that will outline details leading up to the event, information on the event and the investigation, and enhancements made by Ajax in response.

I let Marc know we need this document no later than Monday, the 16th.

Bill/Marc-if you have any questions please contact me. The information you prepare can be distributed to all copied here.

Thank you.,

**Ron Ford**  
[rford@otbconsultinginc.com](mailto:rford@otbconsultinginc.com)  
813.205.9774

**Otb Consulting, Inc.**  
305 South MacDill Avenue  
Tampa, FL 33609  
[www.otbconsultinginc.com](http://www.otbconsultinginc.com)

NOTICE: PRIVILEGED AND CONFIDENTIAL ATTORNEY WORK PRODUCT:

This e-mail message is intended only for the personal use of the recipient(s) named above. This message may be an attorney-client communication and as such privileged and confidential. If you are not an intended recipient, you may not review, copy or distribute this message. If you have received this communication in error, please notify us immediately by e-mail and delete the original message and any attachments.

**An Ajax Building Corporation  
Incident Investigation Report**



*Tampa Office*

109 Commerce Boulevard  
Tampa, Florida 34677  
813.792.3900 Phone  
813.792.3938 Fax  
[www.ajaxbuilding.com](http://www.ajaxbuilding.com)

CG C042112

**Quinlan Enterprises  
Crane Collapse  
St Petersburg Police Facility Project  
April 5, 2018**

*By Marc Reeves  
Ajax Building Corporation  
Director of Risk Management  
[marc@ajaxbuilding.com](mailto:marc@ajaxbuilding.com)*

**April 12, 2018**

## Incident Summary

---

**Date:** April 5, 2018

**Time:** 8:07am

**Incident Location:** St Petersburg Police Facility / EOC - Project Number 201522

**Incident Address:** 1301 1<sup>st</sup> Ave. North St. Petersburg, Fl. 33705

**Parties Involved:**

Construction Manager:

Ajax Building Corporation  
109 Commerce Blvd.  
Oldsmar, Fl. 34677  
813.792.3900 – Bill Byrne: President  
850.251.9227 – Marc Reeves: Risk Management

Structural Steel Fabricator:

Trinity Steel Fabricators  
825 Corporate Square Drive  
Green Cove Springs, Fl. 32043  
904.284.9657 – Damon Westfall: Project Manager

Structural Steel Erector:

Quinlan Enterprises  
514 Mary Lee St.  
Claxton, Ga. 30417  
912.964.2458 – John Quinlan: Owner  
Mike Quinlan: Crane Operator

**Description of Incident:**

Mike Quinlan, crane operator for Quinlan Enterprises, was directed to make a lift off of the 3<sup>rd</sup> floor (2<sup>nd</sup> floor roof) of the northwest corner of the SPPD admin building. After the load was hooked up Mr. Quinlan began the lift and swung the crane right, away from the building. As the crane swung right, Mr. Quinlan, felt the crane beginning to tip. He attempted to lower the load but was not able to do so in time. The crane rotated over its right track onto its side and the boom fell across the jobsite to the west.

**Injuries Associated with this Incident:**

None

**Damage to Structures / Equipment:**

No damage to structures. The crane did not strike the building or any other structures. The only damage associated with this incident is to the crane itself and the load being lifted at the time.

### **Lift Details:**

#### Crane:

Manufacturer: Terex

Model: HC-110

Serial Number: AC4173

Max Capacity: 110 Tons

Boom Length: 240' (180' main boom + 60' jib)

\*specifications / load chart attached

#### Crane Load:

Manufacturer: JLG (Elec Scissor Lift)

Model: 2632ES

Serial Number: M200003399

Weight: 4,629lbs

\*specifications / pictures attached

#### Site / Lift Layout and Lift Radius:

Pick radius: 182' (from the center pin of the crane to the load)

\*see attached site / lift layout drawing

#### Lift Detail Summary / Findings

Per the attached load chart for the configuration of the crane at the time of the incident, the maximum lift capability at the pick radius was 3,370lbs. The weight of the JLG scissor lift (4,629lbs) exceeded the cranes capacity by 1,259lbs. As the crane boomed right from the toe of the right track toward the side of the track it tilted past its axis and rolled onto its side.

### **Timeline / Sequence of Activities for Trinity / Quinlan Enterprises**

#### **March 2017**

During the pre-construction phase of the SPPD project Trinity Fabricators Inc. completed the Ajax Building Corporation prequalification process and was determined to be qualified to bid on this project based on experience, safety record, financial stability and capability, bond capacity, and references.

#### **July 7, 2017**

Ajax Building Corporation contracted with Trinity Steel Fabricators Inc. to provide and erect structural steel for the New St. Petersburg Police Facility / EOC project.

Trinity Steel Fabricators subcontracts the erection of the structural steel to Quinlan Enterprises.

This establishes the contractual relationships between the parties involved. There was no direct contractual relationship between Ajax Building Corporation and Quinlan Enterprises



### **November 14, 2017**

The structural steel pre-construction meeting was held at the jobsite trailer. Representatives from Ajax, Trinity, Quinlan, St. Petersburg Police Dept., and the City of St. Petersburg were in attendance.

\*excerpts from meeting minutes:

➤ **Scheduled Crane Specs**

- Erection company will be Quinlan Enterprises. Crane and rigging are owned by Quinlan. Quinlan provided safety manuals to Ajax. The scheduled crane is a 110-ton w/ 150' of main boom. There is the capability to add 40' of boom if required due to the panel bracing item below. Crane delivery is to TBD with additional coordination needed with Ajax

➤ **Crane Inspections**

Ajax advised that the following info is required:

- Annual certification
- Operator certification
- Rigging to be tagged
- Riggers & signalmen cards/certs

➤ **Tie-off & Leading Edge Work**

- Quinlan confirmed that they will abide by all applicable OSHA standards. Will confirm that the setback for tie off is 15' from the leading edge.

\*full meeting minutes are attached.

### **December 2017**

Quinlan Enterprises mobilizes on site.

As required per Ajax Building Corporations Safety Management Program, upon completion of buildup of the crane, a 3<sup>rd</sup> party independent crane inspection was performed by the Crane Institute of America. This inspection was conducted on 12/16/17.

\*inspection report attached.

Quinlan Enterprises identified Ray-Paul Rougeau as the crane operator for the project.

\*copy of NCCCO certification attached

### **January 17, 2018**

Quinlan Safety Violation #1

Per Ajax Building Corporation subcontract attachment B-2 excerpt\*

A critical lift is defined as any lift in which one of the following conditions are present:

- Where in the cranes current configuration at any point during the lift, the gross load weight exceeds 75% of the capacity of the crane, or 85% of the capacity of the crane where tilt panels are being erected.
- A single lift in which two or more cranes are being used. (tandem lifts)



- Lifts made within 20' of energized power lines.
- Hoisting personnel in suspended work platforms.
- Lifts involving, specialized material/equipment or unique and complex rigging equipment.
- Static tower crane erection and dismantlement.

Where a critical lift will be performed, a written critical lift plan shall be submitted to Ajax Building Corporation prior to commencing with the lift.

### Violation

During review of steel erection activities a W36x150 x70' beam with a tagged weight of 11,335lbs was identified on site. This beam was identified as a critical lift due to exceeding 75% of the cranes capacity at the pick radius. Quinlan Enterprises submitted a critical lift worksheet for review. The worksheet which was submitted had the load incorrectly listed at 10,645lbs and did not account for rigging, hook, block, or load line weights. Quinlan was directed to not make the lift until a corrected lift plan was submitted and approved. On January 17, 2018 Quinlan Enterprises set the referenced beam without an approved lift plan as required.

\*see attached submitted (incorrect) lift plan and related e-mails concerning unapproved lift.

### **January 31, 2018**

#### **Quinlan Safety Violation #2**

The crane operator, Ray-Paul Rougeau, was moving the crane location when the head ache ball retracted into the jib causing the approximately 35' section of the jib to snap off of the main boom of the crane and hang from the cable. No load was being picked at the time. The "anti-two blocking device" malfunctioned because it did not cause the cable to stop before the head ache ball retracted into the jib. In addition the crane operator thought that the cable was not engaged however the cable lever must have not being fully locked into the disengaged position causing the cable to continue to retract. There was no injuries or damage to the project or property with the exception of the crane boom suffering significant damage.

\*see attached incident report

As the crane boom suffered significant damage Ajax instructed Trinity and Quinlan that, once repaired, the crane would have to have another 3<sup>rd</sup> party independent safety inspection prior to being returned to service. This inspection was performed by the Crane Institute of America on 2/6/18.

\*see attached inspection report

As a result of this incident Ajax Building Corporation instructed Trinity Steel Fabricators to have Quinlan Enterprises replace the crane operator. Mr. Rougeau was terminated and replaced with Mike Quinlan

\*see attached NCCCO certification

**February 7, 2018**

**Quinlan Violation #3 – Fall Protection**

On February 7, 2018 Ajax safety department conducted a safety inspection at the SPPD project. Quinlan Enterprises was observed in violation of fall protection requirements. Excerpt of Ajax safety inspection report below.

**Steel Erection**

**Basic Requirements:** Fall Protection: Connectors and Deck installers – 15 feet up to 30 feet or 2 stories whichever is less - Site Layout: Adequate access, firm, level, graded, and drained storage - Commencement of steel erection: Concrete test reports - Hoisting and Rigging: Pre shift inspections (See cranes and rigging) - Column Anchorage: 4 bolts min. Notification of anchor bolt repair or modification - Beams and Columns: 2 bolts per connection min. prior to release by crane, Double connections - Bar Joist:

**Violations:**

**Ajax Building Corporation Subcontract Attachment B1 - Structural Steel Erectors:** Shall submit a written site-specific fall protection plan for review prior to beginning work. Any employee engaged in steel erection activities on a walking/working surface 15 feet or more above a lower level shall be protected from falling. No exceptions. Controlled Decking Zone (CDZ), A CDZ shall be established in the area of the structure 15 feet or more above a lower level where metal decking is initially being installed and forms a leading edge. Any employee engaged in decking activities shall be tied off at all times when working 15 feet or more above a lower level inside a CDZ. Employees behind the CDZ do not have to be tied off provided there is perimeter and floor opening protection installed.



**Comments / Corrective Action during the Inspection:**

Pictures 1 Controlled decking zone not installed as required.

Picture 2 Steel erector not tied off as required. Worker was permanently removed from the project. We conducted a meeting with Allan, superintendent of Quinlan Enterprises, to discuss safety violations from today's inspection. Any personnel not tied off will be removed from the project. The control decking zone will be established by the morning of 2/8 or Ajax will procure the materials and back charge for such.



### February 9, 2018

As a result of the three violations above Ajax instructed Trinity to issue a final safety warning to Quinlan noting that any further violations will result in dismissal from the project and termination of their contract. This notice also required that Quinlan hire and have a full time safety supervisor on site at all times.

\*see attached final safety warning notice from Trinity to Quinlan.

### March 29, 2018

#### Quinlan Final Safety Violation


On March 27 & 28, 2018 Ajax safety department conducted a safety inspection at the SPPD project. Quinlan Enterprises was observed in violation of fall protection requirements. Excerpt of Ajax safety inspection report below.

#### **Steel Erection**

**Basic Requirements:** Fall Protection: Connectors and Deck installers – 15 feet up to 30 feet or 2 stories whichever is less - Site Layout: Adequate access, firm, level, graded, and drained storage - Commencement of steel erection: Concrete test reports - Hoisting and Rigging: Pre shift inspections (See cranes and rigging) - Column Anchorage: 4 bolts min. Notification of anchor bolt repair or modification - Beams and Columns: 2 bolts per connection min. prior to release by crane, Double connections - Bar Joist:

#### **Violations:**

**Ajax Building Corporation Subcontract Attachment B1 - Structural Steel Erectors:** Shall submit a written site-specific fall protection plan for review prior to beginning work. Any employee engaged in steel erection activities on a walking/working surface 15 feet or more above a lower level shall be protected from falling. No exceptions. Controlled Decking Zone (CDZ), A CDZ shall be established in the area of the structure 15 feet or more above a lower level where metal decking is initially being installed and forms a leading edge. Any employee engaged in decking activities shall be tied off at all times when working 15 feet or more above a lower level inside a CDZ. Employees behind the CDZ do not have to be tied off provided there is perimeter and floor opening protection installed.



**Comments / Corrective Action during the Inspection:**

Photo #1 – Steel erector was observed on the edge of the roof deck without being tied off as required.

Photo #2 – Steel erector was observed using a lanyard as a beam strap to anchor a retractable lanyard.

As per the final warning notice issued to Quinlan on 2/9/18, Trinity Steel Fabricators was instructed to remove Quinlan Enterprises from the SPPD project.

**March 30, 2018**

Trinity Steel Fabricators contracts with and mobilizes Florida Atlantic complete the steel erection at the SPPD project.

**April 5, 2018**

Date of incident. During demobilization activities Quinlan Enterprises attempted to lift a load in excess of the rated capacity for the crane at the lift radius resulting in the crane tipping over.

\*see attached operators written statement

**April 5 / 6 2018**

Upon notification of the incident, Ajax instituted its crises / recovery program in order to limit any additional impact to the project. North American Crane Co. was mobilized to assist with righting the crane. Crews worked through the night and had the crane disassembled and upright in less than 24 hours after the incident. There were no impacts or lost time to the project due to this incident.

**Summary and Findings****Pre-Construction Phase:**

All required pre-construction activities were performed.

- Trinity Steel Fabricators has completed numerous Ajax projects and was pre-qualified as required for this project
- As is common in the industry, Trinity subcontracted the erection portion of their contract.
- All safety requirements were communicated to Quinlan Enterprises prior to mobilization during the pre-construction meeting.
- Quinlan Enterprises provided all required documentation, including but not limited to, 3<sup>rd</sup> party independent crane inspections and crane operator certifications prior to beginning work on site.



### Construction Phase:

Steel erection activities were closely monitored and as issues were observed Ajax utilized a graduated system of enforcement in order to ensure Quinlan Enterprises maintained compliance with all required safety regulations.

- Written safety violation notice
- Removal and replacement of the crane operator
- Required to hire a full time safety supervisor for this project
- Removal and termination of erection contractor due to fall protection violations.

As the system of graduated enforcement did not achieve the desired results, Quinlan was removed from the project and their contract with Trinity was terminated. The incident on April 5, 2018 occurred while Quinlan was demobilizing.

### Moving Forward / Ajax Program Enhancements

As a result of Quinlan Enterprises complete lack of regard concerning jobsite safety on the St Petersburg Police Facility project:

- Trinity Steel Fabricators removed Quinlan from consideration on the Ajax Building Corporation FSU EOAS project in Tallahassee.
- Quinlan Enterprises will not be allowed on any Ajax Building Corporation projects in the future.
- To further enhance the Ajax Building Corporation safety management program, beginning immediately, Ajax will require all subcontractors, which subcontract portions of their scope of work to lower tiered subcontractors, to review and submit the OSHA safety compliance history of these lower tiered subcontractors to Ajax for review.

**-End of Report-**

### Attachments

---

Terex HC 110 Crane Specifications and Load Chart – 8 pages  
JLG 2632ES Electric Scissor Lift Specifications – 3 pages  
Picture of JLG 2632ES Manufacturers Plate - 1 page  
Site Layout / Lift Radius – 1 page  
Pre-Construction Structural Steel Meeting Minutes – 4 pages  
12/16/17 3<sup>rd</sup> Party Independent Crane Inspection Report – 4 pages  
Ray-Paul Rougeau NCCCO Certification – 1 page  
Critical Lift Worksheet dated 1/15/18 – 4 pages  
1/31/18 Incident Report – 4 pages  
2/6/18 3<sup>rd</sup> Party Independent Crane Inspection Report – 4 pages  
Mike Quinlan NCCCO Certification – 2 pages  
Trinity Fabricators Final Warning Notice – 3 pages  
Quinlan Crane Operators Statement – 1 page



**TEREX®**



*The Lifting Professionals*

Bolingbrook, IL  
(630) 972-9199

South Holland, IL  
(219) 972-9199

[Click Here to Request a Quote](#)

**HC 110**  
110 USt capacity  
Hydraulic crawler crane  
Datasheet  
imperial


# HC 110



**WORKS FOR YOU.™**


# DIMENSIONS

HC 110



# DIMENSIONS

HC 110





# RANGE DIAGRAM

HC 110

59HI Boom, #9HL Jib



# LOAD CHART

HC 110

With 59HI Offset Tip Boom – 4 Sheave Tip, #9HL Jib

52,900 lb + 23,000 lb SC								360°								ANSI B 30.5							
60' (18.3 m) Jib length																							
Boom length	Jib Radius (Feet)	5.0 Deg offset Boom Angle	Rating (Pounds)	15.0 Deg offset Boom Angle	Rating (Pounds)	25.0 Deg offset Boom Angle	Rating (Pounds)	Boom length	Jib Radius (Feet)	5.0 Deg offset Boom Angle	Rating (Pounds)	15.0 Deg offset Boom Angle	Rating (Pounds)	25.0 Deg offset Boom Angle	Rating (Pounds)								
150' (45.7 m)	42	81.0	15,360*	-	-	-	-																
	50	78.8	14,930*	-	-	-	-																
	60	76.0	14,330*	78.7	12,880*	-	-																
	70	73.2	13,790*	75.9	12,470*	78.4	11,300*																
	80	70.3	13,300*	73.0	11,980*	75.5	10,950*																
	90	67.4	12,800*	70.0	11,530*	72.5	10,620*																
	100	64.4	12,230*	67.0	11,170*	69.4	10,320*																
	110	61.3	10,570	63.9	10,570	66.2	10,080*																
	120	58.1	9,170	60.7	9,170	63.0	9,180																
	130	54.8	7,990	57.4	7,990	59.6	8,000																
	140	51.4	6,990	53.9	6,990	56.0	7,000																
	150	47.7	6,130	50.2	6,140	52.3	6,140																
160' (48.8 m)	44	80.9	15,280*	-	-	-	-																
	50	79.3	14,940*	-	-	-	-																
	60	76.6	14,400*	79.2	12,910*	-	-																
	70	73.9	13,890*	76.5	12,570*	78.9	11,360*																
	80	71.2	13,440*	73.8	12,090*	76.2	11,010*																
	90	68.4	12,970*	71.0	11,690*	73.3	10,660*																
	100	65.6	12,020	68.1	11,280*	70.4	10,400*																
	110	62.7	10,300	65.2	10,310	67.5	10,140*																
	120	59.7	8,890	62.2	8,890	64.4	8,900																
	130	56.6	7,710	59.1	7,710	61.2	7,720																
	140	53.4	6,710	55.8	6,710	57.9	6,720																
	150	50.1	5,850	52.5	5,860	54.5	5,860																
	160	46.5	5,120	48.9	5,120	50.8	5,120																
170' (51.8 m)	46	80.8	15,200*	-	-	-	-																
	50	79.8	15,010*	-	-	-	-																
	60	77.2	14,470*	79.7	12,920*	-	-																
	70	74.7	13,970*	77.1	12,610*	79.5	11,390*																
	80	72.1	13,510*	74.5	12,210*	76.8	11,070*																
	90	69.4	13,120*	71.9	11,790*	74.1	10,760*																
	100	66.7	11,770	69.2	11,380*	71.4	10,470*																
	110	64.0	10,060	66.4	10,060	68.6	10,060																
	120	61.2	8,650	63.5	8,650	65.7	8,650																
	130	58.3	7,460	60.6	7,470	62.7	7,470																
	140	55.3	6,460	57.6	6,470	59.6	6,470																
	150	52.2	5,600	54.5	5,610	56.4	5,610																
	160	48.9	4,870	51.2	4,870	53.1	4,870																
	170	45.5	4,220	47.7	4,220	49.5	4,230																
* see page 17 „Notes to lifting capacity“																							

Boom length	Jib Radius (Feet)	5.0 Deg offset Boom Angle	Rating (Pounds)	15.0 Deg offset Boom Angle	Rating (Pounds)	25.0 Deg offset Boom Angle	Rating (Pounds)
180' (54.9 m)	47	80.9	15,170*	-	-	-	-
	50	80.2	15,030*	-	-	-	-
	60	77.8	14,540*	80.1	12,970*	-	-
	70	75.3	14,050*	77.7	12,640*	79.9	11,460*
	80	72.8	13,640*	75.2	12,320*	77.4	11,130*
	90	70.3	13,200*	72.7	11,890*	74.8	10,840*
	100	67.8	11,510	70.1	11,510	72.2	10,560*
	110	65.2	9,790	67.5	9,790	69.5	9,800
	120	62.5	8,380	64.8	8,380	66.8	8,390
	130	59.7	7,200	62.0	7,200	64.0	7,200
	140	56.9	6,200	59.2	6,200	61.1	6,200
	150	54.0	5,340	56.2	5,340	58.1	5,340
	160	51.0	4,590	53.2	4,590	55.0	4,600
	170	47.8	3,940	49.9	3,940	51.7	3,950
	180	44.4	3,370	46.5	3,370	48.2	3,370
190' (57.9 m)	49	80.8	15,040*	-	-	-	-
	50	80.6	14,990*	-	-	-	-
	60	78.3	14,550*	80.5	12,920*	-	-
	70	75.9	14,080*	78.2	12,620*	80.3	11,440*
	80	73.5	13,650*	75.8	12,330*	77.9	11,180*
	90	71.1	13,290*	73.4	12,000*	75.5	10,870*
	100	68.7	11,250	70.9	11,250	73.0	10,610*
	110	66.2	9,530	68.4	9,530	70.4	9,530
	120	63.7	8,110	65.9	8,120	67.9	8,120
	130	61.1	6,940	63.3	6,940	65.2	6,950
	140	58.4	5,930	60.6	5,930	62.5	5,940
	150	55.7	5,080	57.8	5,080	59.7	5,090
	160	52.8	4,330	54.9	4,330	56.7	4,340
	170	49.9	3,680	51.9	3,680	53.7	3,690
	180	46.8	3,100	48.8	3,110	50.5	3,110
	190	43.5	2,600	45.5	2,600	47.1	2,610
200' (61.0 m)	50	80.9	15,000*	-	-	-	-
	60	78.7	14,550*	80.9	12,920*	-	-
	70	76.5	14,090*	78.7	12,660*	80.7	11,200*
	80	74.2	13,710*	76.4	12,380*	78.4	11,200*
	90	71.9	13,120	74.1	12,090*	76.1	10,940*
	100	69.6	10,980	71.7	10,990	73.7	10,650*
	110	67.2	9,260	69.3	9,260	71.3	9,270
	120	64.8	7,850	66.9	7,850	68.8	7,850
	130	62.3	6,660	64.4	6,670	66.3	6,670
	140	59.8	5,660	61.8	5,660	63.7	5,670
	150	57.2	4,800	59.2	4,800	61.0	4,810
	160	54.5	4,060	56.5	4,060	58.3	4,070
	170	51.7	3,400	53.7	3,410	55.4	3,410
	180	48.8	2,830	50.8	2,830	52.5	2,830
	190	45.8	2,320	47.7	2,320	49.3	2,330
	200	42.6	1,860	44.5	1,870	46.0	1,870

\* see page 17 „Notes to lifting capacity“

# NOTES TO LIFTING CAPACITY

HC 110

## Warning

This rating chart is invalid if the crane has been modified or altered by use of other than GENUINE AMERICAN PARTS as such modifications or alterations may affect its capacity or safe operation. See American Crane Corporation Service Bulletin #259.

Ratings in this chart are in POUNDS and do not exceed the percentage of tipping specified for this crane by ANSI B30.5. All ratings require that the crane be standing level on a firm uniformly supporting surface.

Do not lift loads in excess of those shown on this chart. Lifting loads in excess of those shown or operation not in accordance with good operating practice, including limitations shown on page 3499 of Operator's Manual, can cause tipping, structural damage or catastrophic failure.

Asterisk (\*) areas on this chart indicate ratings that are limited by strength of material or factors other than stability (tipping).

„RADIUS IN FEET“ is the horizontal distance at ground level from the crane centerline of rotation to a vertical line through the center of gravity of the suspended load.

When using the main boom fall with jib in place, the main fall ratings must be reduced by the jib effective weight shown on the jib rating chart plus twice the weight of all suspended blocks, slings, rope, etc., at the jib fall. See Appendix A.

When using the main boom fall with boom tip extension in place, the main fall ratings must be reduced by the weight of the boom tip extension plus twice the weight of all suspended blocks, slings, rope, etc., at the boom tip extension fall. See Appendix A.

Blocks, slings, buckets and other load carrying devices are considered part of the load. The weight of standard hoisting ropes for the rating at a given radius has been calculated as part of the boom point load and need not be considered in determining net allowable loads. See Appendix A.

Ratings shown on this chart make no allowance for such factors as out of plumb loads, wind, poor soil conditions, improper inflation of rubber tires and dynamic effects due to excessive operating speeds. The user (operator) must exercise judgment to make allowance for these conditions. See page 3499 of Operator's Manual for detailed information.

No account is taken of the wind force on the load. This effect, which can be substantial for loads with large surface areas, must be considered by the user. In any wind it is strongly recommended that taglines be used to control the load.

BOOM HOIST LINE – 12 parts of 3/4 inch diameter IPS wire rope with a minimum breaking strength of 51,200 pounds.

PENDANT SUSPENSION LINE – 2 parts of 1-3/8 inch diameter EEIPS wire rope with a minimum breaking strength of 211,000 pounds.




JIB BACKSTAY AND FRONTSTAY LINES – 2 parts of 0.875 inch diameter IPS wire rope with a minimum breaking strength of 69,200 pounds.

JIB WHIP LINE – 7/8 inch diameter EIPS wire rope with a minimum breaking strength of 79,600 pounds.

## SIDEFAME POSITION DEFINITIONS

These ratings are valid for the sideframe positions as indicated below.

Refer to the HC 110 Operator's Manual for additional information.



## ERECTION

Erection „OVER-THE-END BLOCKED“

is with the boom over the idler end with idler tumblers blocked (See HC 110 Operator's Manual for blocking instructions). Erection „OVER-THE-SIDE“ is with the boom 90° to the sideframes. Blocks, slings and other load carrying devices must be on the ground during erection.

59HI OFFSET TIP BOOM MAXIMUM BOOM & JIB SELF-ERECTION DATA				
JIB	OVER-THE-END BLOCKED		OVER-THE-SIDE	
			SIDEFRAMES FULLY-EXTENDED (WITH EXTENDERS IN PLACE)	
	BOOM LENGTH (FEET)	JIB LENGTH (FEET)	BOOM LENGTH (FEET)	JIB LENGTH (FEET)
9HL	230	0	210	0
	220	0	200	0
	210	40	190	40
	200	70	180	70

BOOM COMPOSITION CHART - 59HI OFFSET TIP					
BOOM LENGTH (FEET)	BOOM SECTIONS				
	25' 59HI INNER	10' 59HI CENTER	20' 59HI CENTER	40' 59HI CENTER	25' 59HI OUTER
100	1	1	0	1	1
110	1	1	0	1	1
120	1	1	1	1	1
130	1	1	0	2	1
140	1	1	0	2	1
150	1	0	1	2	1
160	1	1	1	2	1
170	1	0	0	3	1
180	1	1	0	3	1
190	1	0	1	3	1
200	1	1	1	3	1
210	1	0	0	4	1

LOAD HOISTING INFORMATION - 7/8" diameter EIPS wire rope			
MAXIMUM LIFTING CAPACITY - LBS.	MINIMUM PARTS OF LINE	MAXIMUM HOISTING DISTANCE - FEET	
		MAIN HOIST	AUX HOIST
22,550	1	N/A	626

9HL JIB COMPOSITION CHART								
JIB LENGTH (FEET)	20' INNER	10' CENTER	20' CENTER	20' OUTER	EFF. JIB WEIGHT (POUNDS)	JIB OFFSET "A" IN FEET & INCHES		
						5'	15'	25'
40	1	0	0	1	1,850	4' 9"	9' 9"	14' 8"
50	1	1	0	1	2,350	5' 5"	11' 8"	17' 9"
60	1	0	1	1	2,750	6' 1"	13' 6"	20' 9"
70	1	1	1	1	3,700	6' 8"	15' 6"	24' 0"

# TECHNICAL DESCRIPTION

HC 110

## Hydraulic Crawler Crane

### Maximum lifting capacity

110 tons (100 mt).

### Boom systems

59HI Tubular Chord Boom, pin connected – with 4 Sheave Tip

- 230 ft maximum boom length.
- 270 ft maximum boom and jib combination length.
- 25 ft (7.6 m) inner and 25 ft (7.6 m) outer and 10 ft / 20 ft / 40 ft available inserts provide boom compositions in 10 ft (3 m) increments from 50 ft (15.2 m) to 230 ft (70 m).

### Robust engine

- Cummins Model QSB 6.7 Turbocharged, after cooler, diesel engine, 4 cycle, 6 cylinders, direct fuel injection, 409 cubic inch displacement, 6.7 liters, 240 BHP @ 2000 rpm, 105 gallons fuel tank capacity.

### Environmental operator's cab

- Designed to provide excellent viewing range and quiet, comfortable operation.
- 37 inch (0.91 m) wide cab has wide curved windows on both top and bottom.
- Easy-to-operate modular and ergonomically designed controls reduce operator fatigue and increase productivity.
- Load Moment Indicator with interactive screen. Operator can select from three display modes: loaded condition diagram, rated lifting curve or rated lifting load table.
- Adjustable operator's seat, radio, air conditioner, overhead window, sun visor, fan, overhead and front wipers and drum rotation indicators are standard.

### Heavy duty carbody and crawlers

- Fabricated steel carbody is deep box constructed with square axles for the crawler side frames. Precision machined top supports anti-friction swing circle and multiple pass hydraulic swivel joint.
- Crawlers have high alloy steel tumbler yokes and rigid fabricated structures with sealed rollers.
- 36" (914 mm) crawler shoes.
- Travel mechanism is set within shoe width.
- Side frames extended or retracted by cylinders inside the carbody.
- Two travel speed settings – 0.60 / 0.87 mph (0.96 / 1.4 km/h).
- 30 % (17°) gradeability.

### Powerful, high-speed hoist system

- Independent main and auxiliary load hoisting drums. Main drum is grooved for 1 inch (25 mm) diameter rope. Max line speed is 513 fpm (156 m/min), max single line pull is 40,640 lb (18 435 kg). Rated single line pull is 29,500 lb (13 381 kg). Auxiliary drum is grooved for 7/8 inch (22.4 mm) diameter rope. Max line speed is 553 fpm (168 m/min), max single line pull is 37,670 lb (17 086 kg). Rated single line pull is 22,700 lb (10 297 kg). Freefall on main and auxiliary drums.
- Each drum, including optional third, has power up/down and freefall. Load hoists are further controllable in stepless mode.
- Ample work space in front of the drums allows easy access for cable installation and maintenance.
- External contracting brake.
- Internal expanding band clutch.
- 3.0 rpm swing speed.

### High capacity, dependable hydraulic system

- Open circuit system has 2 variable displacement piston pumps with system capacity of 183 gpm (692 lpm).
- Hydraulic reservoir with 79 gallons (300 l) capacity and 10 micron filtration.
- Component working range is between -4 and 203° F (-20 and 95° C).

### Four piece removable counterweight

- Four piece pin connected counterweight can be assembled or disassembled easily within minutes.
- Hydraulic counterweight removal system is standard and makes the HC 110 one of the most transportable cranes in its class.
- Moves on five trucks with full boom and #9HL jib. At 17 ft, 0.5 inch (5.2 m) wide and 11 ft (3.35 m) high, the basic HC 110 will transport on a standard lowboy trailer.

### Options include

- |                                 |                           |
|---------------------------------|---------------------------|
| – Third drum                    | – Single sheave extension |
| – Third drum with free spooling | – Transportation package  |
| – Automotive type lights        | – Single sheave extension |
| – Hydraulic power take off      | – Tagline winder          |
| – Jib and jib inserts           |                           |





# TRANSPORT EXAMPLE FOR HC 110

HC 110

## With 200 ft 59"H Boom & 70 ft Jib and 3rd Drum

Loads required as follows (weights shown do not include blocking or tie-down material):

### LOAD NO. 1 – Step Deck

2 x crawler side frame counterweights (11,500 each) .....	23,000 lbs
40' boom center section with pendants .....	2,670 lbs
20 ft jib inner .....	890 lbs
1 x upper counterweight .....	4,400 lbs
<b>TOTAL LOAD .....</b>	<b>30,960 lbs</b>

### LOAD NO. 2 – Step Deck

Middle portion of counterweight .....	12,100 lbs
40' boom center section .....	2,670 lbs
20 ft jib outer .....	480 lbs
1 x upper counterweight .....	4,400 lbs
<b>TOTAL LOAD .....</b>	<b>19,650 lbs</b>

### LOAD NO. 3 – Step Deck

Lower portion of counterweight .....	32,000 lbs
25 ft boom outer section .....	4,200 lbs
20' boom center section .....	1,975 lbs
Main load block .....	1,500 lbs
Overhaul ball .....	650 lbs
<b>TOTAL LOAD .....</b>	<b>40,325 lbs</b>

### LOAD NO. 4 – Step Deck


1 x 10' boom center section .....	1,060 lbs
1 x 40' boom center sections .....	2,670 lbs
10' jib center section .....	190 lbs
20' jib center section .....	385 lbs
<b>TOTAL LOAD .....</b>	<b>4,305 lbs</b>

### LOAD NO. 5

#### Basic Crane:


- a) Complete upper structure
- b) Carbody and sideframes
- c) Retractable A-frame
- d) Boom inner section and boom stops
- e) Third drum

<b>TOTAL WEIGHT OF BASIC CRANE, etc.) .....</b>	<b>105,000 lbs</b>
---	--------------------



## 2632ES

### Electric Scissor Lift



\* Scissor lift  
Info - sat to  
structural engineer  
for Approval on Deck  
weight

## Key Specs

- Platform Height: 25 ft 6 in. / 7.77 m
- Machine Width: 2 ft 8 in. / 0.81 m

## Power Source

Batteries	4 x 6V, 220 amp-hour
Charger	20 amp automatic

## General

Brakes	Electric, Friction
Capacity - Hydraulic Reservoir	1 gal. / 4.73 L
Maximum Ground Bearing Pressure	90 psi / 6.30 Kg/cm2
Hydraulic Pump	Fixed Displacement Gear
Machine Weight	4635 lb / 2102.40 kg

# Note  
4629 lbs per  
Lift Tag -  
Attached

## Performance

Drive Speed - Platform Elevated	1 mph / 0.80 km/h
Drive Speed - Platform Lowered	3 mph / 4.43 km/h
Drive System	24V Electric
Gradeability	25 %
Lift Time	33 sec.
Lower Time	37 sec.
Maximum Drive Height	25 ft 6 in. / 7.77 m
Platform Capacity - Extension	250 lb / 113.40 kg
Platform Capacity - Restricted	800 lb / 362.87 kg
Platform Capacity - Unrestricted	500 lb / 226.80 kg
Turning Radius - Inside	0 in. / 0 m
Turning Radius - Outside	6 ft 9 in. / 2.06 m

## Dimensional Data

Ground Clearance	4 in. / 0.09 m
Machine Height	7 ft 8 in. / 2.33 m
Machine Height - Rails Folded	6 ft 5 in. / 1.94 m

## Dimensional Data

Machine Length	7 ft 7 in. / 2.3 m
Machine Width	2 ft 8 in. / 0.81 m
Platform Dimension A	2 ft 6 in. / 0.76 m
Platform Dimension B	7 ft 7 in. / 2.3 m
Platform Extension Length	3 ft / 0.9 m
Platform Height - Lowered	4 ft 1 in. / 1.23 m
Platform Railing Height	3 ft 7 in. / 1.1 m
Tire Size	16 X 5 in
Wheelbase	6 ft 2 in. / 1.88 m

## Reach Specifications

Platform Height	25 ft 6 in. / 7.77 m
Working Height	31 ft 6 in. / 9.6 m

## Key Features

- Quieter, cleaner operation for a variety of environments
- Electric drive and integrated components with only two hydraulic hoses and four hydraulic fittings on the entire machine will keep you on the job longer and reduce your operating costs by reducing chances for leaks and service calls
- Narrow width fits through most standard doorways and tight aisles
- Delivers 200% more battery life\*

\*Compared to a competitive model under similar test conditions. Actual results may vary.




MODEL		2632ES		SERIAL NO.		H2000005709	
NOM. BATT. VOLTAGE		24 V.D.C.		MODEL YEAR		2016	
MACHINE WEIGHT	1520 LBS 693 kg	MAX. PLATFORM HEIGHT	25 FT 7 m	RATED WORK LOAD	5000 LBS 2270 kg	MAX. TRAVEL HEIGHT	25.5 FT 7.77 m

RATED WORK LOAD BASED ON FIRM LEVEL SURFACE AND INCLUDES ALL STANDARD ACCESSORIES  
THIS MACHINE MEETS OR EXCEEDS APPLICABLE REQUIREMENTS OF ANSI A92.6-2006 AS ORIGINALLY  
MANUFACTURED FOR INTENDED PURPOSES

Manufactured for JLG Industries Inc. by  
Jishkosh Equipment Manufacturing De Mexico, S. De R.L. de C.V.  
Blvd. Las Joyas, No. 4499,  
Parque Industrial Colinas de León  
León, Guanajuato, México 37668

1001197985 B





Steel  
A preconstruction Meeting



## St. Petersburg Police Facility/EOC Structural Steel Kick-Off Meeting Minutes November 14, 2017, 1:30 pm

### ❖ Introductions

Introductions were completed. See attached sign-in sheet for attendees

### ❖ Safety

#### ➤ Scheduled Crane Specs

- Erection company will be Quinlan Enterprises. Crane and rigging are owned by Quinlan. Quinlan provided safety manuals to Ajax. The scheduled crane is a 110-ton w/ 150' of main boom. There is the capability to add 40' of boom if required due to the panel bracing item below. Crane delivery is to TBD with additional coordination needed with Ajax

#### ➤ Crane Inspections

Ajax advised that the following info is required:

- Annual certification
- Operator certification
- Rigging to be tagged
- Riggers & signalmen cards/certs

#### ➤ Tie-off & Leading Edge Work

Quinlan confirmed that they will abide by all applicable OSHA standards. Will confirm that the setback for tie off is 15' from the leading edge.

### ❖ Structural Steel

#### ➤ Erector & Welding Certifications

Trinity to forward welder certs for record. Quinlan advised there would be 12-14 total workers w/ 5-6 of those being welders. COSP asked John with Quinlan whether he thought the same welders would be on-site for the entire process in order to keep consistent workflow and quality. Quinlan advised that replacing welders is a possibility due to needs of other projects. However, John advised that due to amount of work this shouldn't be an issue as long as the work-flow is not interrupted and welders must be relocated to other jobs

#### ➤ Shop Inspections / AISC Certification

Trinity to forward to Ajax

#### ➤ AESS Steel

##### ▪ Submittals/Samples

Trinity to complete samples for architect review. Sample(s) shall be completed to one standard, i.e. standard for viewing closest to eye-level

- **Protection, Delivery & Installation**

- Primer to be shop-applied. Nylon straps shall be utilized to prevent damage

- **Clips for Curtain Walls**

- To be field-installed after curtain-wall layout due to precision needed. The team had no issue with this

- **Structural Steel to Receive Sprayed-Applied Fireproofing**

- Structural Steel scheduled to receive SAFF shall be delivered un-primed and coordinated with the contract documents

- **Erection**

- **Schedule/Work Flow**

- ◆ CIP shear walls A & B to be topped-out by 12/4. Erectors to mobilize 12/4. Steel Erection shall be W to E for the Admin wing and south to north for Annex.
  - ◆ Schedule  
Schedule to follow Ajax overall schedule sequence and durations which includes erection in Admin building and Annex building going concurrently as well as CEP schedule to start 1/10. Sally port tilt walls will be erected with CEP building so that steel will not go w/ main building 1<sup>st</sup> floor.
  - ◆ Ajax requested that embed locations be surveyed by Trinity ASAP when they mobilize to get ahead of any layout issues before they delay the project.

- **Crane Access vs Tilt-Wall Bracing (review bracing hand-out)**

- ◆ Bracing plan was distributed for review. Trinity/Quinlan to review closely as most tilt-panel bracing is scheduled for exterior installation. This will have an impact on the crane's position to the building and available reach. They are to advise Ajax on any impacts or if no issues are anticipated
  - ◆ Trinity/Quinlan to forward different pick scenarios with weights for review. This should include the longest radius pick and heaviest steel member

- **Post Erection Camber Surveys**

- Ajax to verify if required

- **Field Quality Control/Inspections**

- **Base Plate Grout & Testing**

- Grout material was submitted on and approved. The product used will be field verified by Ajax prior to installation and all grouted columns will have photograph documentation

- **Bolt and Weld Inspections**

- Tierra will be completing inspections and requested a 48-hr notice. 1<sup>st</sup> inspection will be called in early to set expectations.

- ❖ **Joists**

- **Primer vs Studs**

- Top chord to be "taped" off prior to primer application so that stud installation can be completed per industry standards

- ❖ **Steel Decking**

- **Schedule/Work Flow**

- 2<sup>nd</sup> floor deck will not be poured until 3<sup>rd</sup> floor steel is completed to allow for adjustments

➤ **Openings/Reinforcing**

Ajax to verify what the contract documents /manuf. requirements are for framing around openings. However, it is anticipated that all openings are to receive some type of reinforcement. Steel sub shall be responsible at the deck level and the concrete sub at the in-fill/topping level

➤ **Attachments methods and welds**

Shall be per the approved submittal

➤ **Shear Stud installation and spacing**

Shall be per the approved submittal

❖ **Stairs**

➤ **Schedule/Work Flow**

Scheduled to follow directly behind the second floor steel. Ajax's plan is to in-fill with concrete as soon as possible after installation.

➤ **Stringer RFI**

Trinity raised concerns in regards to stair submittal note by HJ about not cutting stringers and advised that they would need to be re-designed if required. Trinity advised that this would delay stair fabrication by weeks. HJ's concern was in regards to keeping a finished look to the stringers. Trinity advised that this would not be an issue and will submit a RFI to clarify and supplement the submittal note

➤ **Railings**

Permanent rails have architectural features that would be highly susceptible to damage if installed and used during construction. Trinity to install temporary stanchions and cables

❖ **Green Globes**

Trinity to forward all required information

❖ **Miscellaneous Items Discussed.**

- Erector will require a concrete release form prior to starting erection activities
- All steel at the CEP will be hot-dipped galvanized. This will add about 1 week to the delivery date
- A ceremonial beam for topping out will be needed. Ajax to determine which beam this will be and provide with a white powder coating. Decals will be supplied by others. Trinity advised that they will complete a temporary install of the beam to ensure the dimensions are correct.
- Jody and Quinlan to walk the site after meeting to review deliveries and lay down.





Date: 11/14/2017

Company & Email

Was Stevens

Ajax Wstevens@ajaxbuilding.com

Daniel Wasirau

Trinity DAMON WESTBROOK training fabricators. u -

MIKE WILSON

ALAN BUILDING CORP.

MIKE KOVACSEV

SPD

Michael McDonald

SPPD

Marc Reeves

A day

Bill Champ

## Ajax

Tim Hurst

Al AX

Justin Pennino

A, ap

John Quinlan

Quinlan Enterprises  
Inc.

Mike Mitzner

AS AX

Tom Rice

Co Sp

~~D~~ CROW

COSP

James C. Gibbs

Tierra, Inc.

Jay Brown

ALAY

704 MILES R/T

Crane  
Institute.  
of AmericaOSHA / ASME ANNUAL/PERIODIC  
INSPECTION CHECKLIST

## Lattice Boom Crane

craneinstitute.com • 3880 St. Johns Parkway • Sanford, FL 32771 • 1-800-832-2726

Owner: <b>QUINLAN ENTERPRISES</b>	Contact Person: <b>JOHN QUINLAN</b>	Date: <b>12-16-17</b>
Location: <b>St. Petersburg, FL</b>	Service Status: <b>Annual</b>	Hours: <b>6165 (Cab)</b>
Make: <b>TETEX</b>	Model: <b>HC-110</b>	Serial Number: <b>AC 4173</b>
Unit ID:	Max. Capacity: <b>110 TONS</b>	Inspector: <b>R. Gardner</b>

Before inspecting crane, lock out/tag out power source.

Consult operator/service manual, service bulletins, etc. for additional inspection items.

Before inspection, crane must be set up away from personnel and power lines, with outriggers/crawlers fully extended and crane leveled on firm ground.

OSHA and ASME allow only qualified and competent persons to inspect cranes. To qualify, inspectors must have been through training, have extensive knowledge and demonstrated ability.

References: O = OSHA 1926 Subpart CC, 1926.601, 1910.180 A = PCSA #4, ASME B30.5, B30.10

Status: ✓ = Satisfactory X = Safety Hazard M = Monitor N/A = Not Applicable

RECEIVED  
AJAX BUILDING CORPORATION  
DEC 18 2017

REFERENCE	ITEM	Status
<b>Historical Data</b>		
O-1926.1412 (e)(3)	1. Monthly Inspection Records	✓
A-B30.5-2.3.1 (a)	2. Maintenance Records	✓
O-1926.1434 (a)	3. Modification Records	NA
A-B30.5-2.2.2 (b)	4. Load Test Records	NA
O-1926.1412 (f)(7)	5. Annual Inspection Record	✓
<b>General</b>		
A-B30.5-2.1.3 (a)	6. Sheet Metal	✓
O-1926.1433 (d)(8)	7. Guards / Covers	✓
O-1926.601(2)(i)&(ii)	8. External Lights	✓
A-B30.5-3.4.7	9. Housekeeping	✓
O-1926.1433 (d)(5)	10. Safety / Warning Decals & Labels	✓
O-1926.1422	11. Hand Signal Chart	✓
	12. Other	
	13. Other	
<b>Driver's Cab &amp; Station</b>		
O-1926.601 (b)(1)	14. Service Brake	NA
O-1926.601 (b)(1)	15. Emergency Brake	
O-1926.601 (b)(1)	16. Parking Brake	
O-1926.601 (b)(2)	17. Headlights	
O-1926.601 (b)(2)	18. Taillights	
O-1926.601 (b)(2)(ii)	19. Brake Lights	
O-1926.601 (b)(3)	20. Audible Warning Device	
O-1926.601 (b)(4)(i)	21. Backup Audible Alarm	
O-1926.1433 (d)(7)(iii)	22. Windows	
O-1926.601 (b)(5)	23. Windshield Wipers	
O-1926.601 (b)(5)	24. Defroster	
O-1926.601 (b)(6)	25. Overhead Protection	
O-1926.601 (b)(7)	26. Housekeeping	
O-1926.1412(f)(2)(xviii)&(xix)	27. Seat	
O-1926.601 (b)(9)	28. Seat Belts	
O-1926.601 (b)(14)	29. Tires	
O-1926.601 (b)(14)	30. Steering Mechanism	
O-1926.601 (b)(14)	31. Operating Controls	
O-1926.601 (b)(14)	32. Safety Devices	
O-1926.601 (b)(14)	33. Fire Extinguisher	

REFERENCE	ITEM	Status
<b>Carrier Power Plant (Lower)</b>		
O-1926.1412 (f)(2)(vi)	34. Performance	NA
O-1926.1433 (d)(9)	35. Exhaust System / Guards & Insulators	
O-1926.1433 (d)(8)	36. Belts	
O-1926.1433 (d)(8)	37. Guards / Covers / Rotat. & Recip. Parts	
	38. Other	
<b>Carrier</b>		
O-1926.601 (b)(14)	39. Transmission	
O-1926.601 (b)(14)	40. Drive Line	
O-1926.1412 (f)(2)(ix)	41. Tires	
O-1926.1412 (f)(2)(i)	42. Main Frame Members	
O-1926.1412 (f)(2)(x)	43. Hydraulic Hoses / Tubing / Fittings	
O-1926.1412 (d)(1)(iv)	44. Hydraulic Fluid Level	
O-1926.1423 (c)(3)(ii)	45. Anti-Skid Surface	
O-1926.1417 (aa)	46. Front Bumper Counterweight	
	47. Other	
<b>Outriggers</b>		
O-1926.1412 (f)(2)(i)	48. Boxes	
O-1926.1412 (f)(2)(i)	49. Beams	
O-1926.1412 (f)(2)(xiii)	50. Cylinders	
O-1926.1412 (f)(2)(xiv)	51. Floats / Pads	
O-1926.1412 (f)(2)(x)	52. Hydraulic Hoses / Tubes / Fittings	
O-1926.1412 (f)(2)(xii)	53. Holding Valves	
O-1926.1412 (f)(2)(iii)	54. Position Locks	
O-1926.1433 (d)(5)	55. Warning Signs	
	56. Other	
<b>Crawler Assembly</b>		
O-1926.1412 (f)(2)(i)	57. Car Body / Side Frames	✓
O-1926.1412 (f)(2)(vii)	58. Chain - Condition / Adjustment	✓
O-1926.1412 (f)(2)(vii)	59. Sprockets / Idlers / Rollers	✓
O-1926.1412 (f)(2)(i)	60. Track Pads / Pins	✓
O-1926.1412 (f)(2)(viii)	61. Travel Locks	✓
O-1926.1412 (f)(2)(viii)	62. Steering Clutches	✓
	63. Other	

References: O = OSHA 1926 Subpart CC, 1926.601, 1910.180 A = PCSA #4, ASME B30.5, B30.10

Status: ✓ = Satisfactory X = Safety Hazard M = Monitor N/A = Not Applicable

REFERENCE	ITEM	Status	REFERENCE	ITEM	Status
<b>Operator's Cab &amp; Station</b>			<b>Rotating Upper Structure (continued)</b>		
O-1926.1412 (f)(2)(xxi)	64. Grab Rails / Steps / Platforms	✓	O-1926.1412 (f)(2)(iv)	116. Main Hoist – Clutches / Brakes	✓
O-1926.1423 (c)(3)(ii)	65. Anti-Skid Surface	✓	O-1926.1412 (d)(1)(vi)	117. Main Hoist – Rope Spooling	✓
O-1926.1433 (d)(7)(iii)	66. Windows	✓	O-1926.1413 (a)(4)(i)(B)	118. Main Hoist – Minimum (2) rope wraps	✓
O-1926.1433 (d)(7)(iii)	67. Windshield Wiper(s)	✓	O-1926.1412 (f)(2)(iv)	119. Aux. Hoist – Clutches / Brakes	✓
O-1926.1433 (d)(7)(ii)	68. Door Restraint	✓	O-1926.1412 (d)(1)(vi)	120. Aux. Hoist – Rope Spooling	✓
O-1926.1433 (d)(6)	69. Fire Extinguisher	✓	O-1926.1413 (a)(4)(i)(B)	121. Aux. Hoist – Minimum (2) rope wraps	✓
O-1926.601 (b)(4)	70. Mirrors	✓	O-1926.1412 (f)(2)(iv)	122. Boom Hoist – Clutches / Brakes	✓
O-1926.1412 (f)(2)(xvii)&(xix)	71. Seat	✓	O-1926.1412 (d)(1)(vi)	123. Boom Hoist – Rope Spooling	✓
A- B30.5-1.8.1 (e)	72. Seat Belts	✓	O-1926.1413 (a)(4)(i)(B)	124. Boom Hoist – Minimum (2) rope wraps	✓
O-1926.1433 (d)(1)	73. Operator's Manual	✓	O-1926.1412 (f)(2)(iv)	125. Boom Hoist – Clutch / Pawls / Ratchets	✓
O-1926.1433 (d)(5)	74. Decals	✓	O-1926.1412 (f)(2)(xi)	126. Swing System / Assembly	✓
O-1926.1407 (g)	75. Electrocution Warning Sign (Inside)	✓	O-1926.1412 (f)(2)(xi)	127. Hydraulic Motors / Valves / Lines / Etc.	✓
O-1926.1422	76. Hand Signal Chart	✓	O-1926.1412 (f)(2)(ii)	128. Drums / Flanges	✓
O-1926.1412 (f)(2)(iv)	77. Swing Brake	✓	O-1926.1412 (f)(2)(iv)	129. Clutch / Brake Protection	✓
O-1926.1412 (f)(2)(iii)	78. Positive Swing Lock	✓	O-1926.1412 (f)(2)(iii)	130. Torque Converter	✓
O-1926.1412 (d)(i)&(ii)	79. Control Function	✓	O-1926.1423 (c)(3)(ii)	131. Anti-Skid Surface	✓
O-1926.1412 (f)(2)(xi)(A)	80. Air Pressure	NA	O-1926.1412 (f)(2)(xxi)	132. Steps / Hand Holds / Platforms	✓
O-1926.1415 (a)(4)	81. Foot Brakes – Latches / Linkage	✓	O-1926.1412 (f)(2)(xx)&(xxi)	133. Access to Cab and Roof	✓
O-1926.1412 (f)(2)(iv)	82. Engine Clutch	✓	O-1926.1412 (f)(2)(x)&(xi)	134. Air System – Compressor / Lines / Etc.	NA
O-1926.1412 (d)(i)&(ii)	83. Accelerator / Throttle Control	✓	O-1926.1412 (f)(2)(i)(B)	135. Counterweight Mounting	✓
O-B30.5-1.6.1 (a)	84. Control Marking	✓	O-1926.1433 (d)(5)	136. Counterweight Warning Sign	✓
<b>Load Chart</b>			O-1926.1407 (g)	137. Electrocution Warning Sign (Outside)	✓
O-1926.1433 (d)(1)	85. Per Configuration	✓		138. Other	
O-1910.180 (c)(2)	86. Durable	✓	<b>Boom Support System</b>		
O-1910.180 (c)(2)	87. Legible	✓	O-1926.1412 (f)(2)(i)	139. Gantry / Mast	✓
O-1910.180 (c)(2)	88. Visible From Operator's Station	✓	O-1926.1415 (a)(2)	140. Boom Stops	✓
O-1910.180 (c)(2)	89. Secured	✓	O-1926.1412 (f)(2)(ii)&(iii)	141. Inner Bail	✓
	90. Other		O-1926.1412 (f)(2)(ii)&(iii)	142. Outer Bail / Equalizer	✓
<b>Safety Devices / Operational Aids</b>			O-1926.1412 (f)(2)(ii)	143. Sheave(s)	✓
O-1926.1415 (a)(7)	91. Horn	✓	O-1926.1412 (d)(1)(vi)	144. Boom Hoist Reeving	✓
O-1926.1416 (e)(1)	92. Boom Angle Indicator	✓		145. Other	
O-1926.1416 (e)(5)(ii)	93. Main Drum Rotation Indicator	✓	<b>Boom</b>		
O-1926.1416 (e)(5)(ii)	94. Auxiliary Drum Rotation Indicator	✓	O-1926.1412 (f)(2)(xvii)	146. Boom Section Identification	✓
O-1926.1412 (f)(2)(v)	95. Load Moment Indicator	✓	O-1926.1404 (m)	147. Boom Section Sequence	✓
O-1926.1416 (e)(4)	96. Load Weight Indicator	✓	O-1926.1404 (m)	148. Boom Section Alignment	✓
O-1926.1416 (e)(1)	97. Radius Indicator	✓	O-1926.1412 (f)(2)(xvii)	149. Warning Decals	✓
O-1926.1415 (a)(1)	98. Crane Level Indicator	✓	O-1926.1412 (f)(2)(i)	150. Spreader Bar	✓
O-1926.1416 (d)(3)	99. Anti-Two Block Device	✓	O-1926.1412 (f)(2)(ii)&(iii)	151. Sheave(s)	✓
O-1926.1416 (d)(1)	100. Boom Hoist Limiting Device	✓	O-1926.1413 (a)(2)(i)(D)	152. Hoist Line Dead End	✓
O-1926.1412 (f)(2)(iv)	101. Boom Hoist Ratchet and Pawl	✓	O-1926.1412 (a)(2)(i)(D)	153. Wire Rope Retainer(s)	✓
O-1926.1416 (e)(5)(i)	102. Outrigger / Stabilizer Position Sensor	NA	O-1926.1412 (f)(2)(iii)	154. Boom Foot Pins / Keepers	✓
O-1926.1416 (e)(2)	103. Luffing Jib Angle Indicator	✓	O-1926.1412 (f)(2)(i)	155. Boom Head Section	✓
<b>Power Plant (Upper)</b>			O-1926.1412 (f)(2)(i)	156. Auxiliary Boom Head	NA
O-1926.1412 (f)(2)(vi)	104. Performance	✓	O-1926.1412 (f)(2)(i)	157. Lattice Members	✓
O-1926.1433 (d)(9)	105. Exhaust System / Guards & Insulators	✓	O-1926.1412 (f)(2)(i)	158. Cord Members	✓
O-1926.1412 (d)(1)(iii)	106. Hoses	✓	O-1926.1412 (f)(2)(i)	159. End Connections / Pins	✓
O-1926.1433 (d)(8)	107. Guards / Covers / Rotat. & Recip. Parts	✓		160. Other	
	108. Other		<b>Jib</b>		
<b>Rotating Upper Structure</b>			O-1926.1415 (a)(3)	161. Stops	✓
O-1926.1412 (f)(2)(iii)	109. Turntable / Bearing	✓	O-1926.1412 (f)(2)(ii)	162. Sheave(s)	✓
O-1926.1412 (f)(2)(iii)	110. Turntable – Rollers / Roller Path	✓	O-1926.1413 (a)(2)(i)(D)	163. Wire Rope Retainer(s)	✓
O-1926.1412 (f)(2)(iii)	111. Ring Gear / Pinion Gear	✓	O-1926.1412 (f)(2)(i)	164. Lattice Members	✓
O-1926.1412 (f)(2)(xi)	112. Hydraulic Pump(s)	✓	O-1926.1412 (f)(2)(i)	165. Cord Members	✓
O-1926.1412 (f)(2)(x)	113. Hydraulic Hoses / Tubing / Fittings	✓	O-1926.1412 (f)(2)(i)	166. End Connections / Pins	✓
O-1926.1412 (f)(2)(xi)	114. Hydraulic Pressure	✓	O-1926.1416 (d)(2)	167. Luffing Jib Stops	✓
O-1926.1412 (d)(1)(viii)	115. Electrical Wiring	✓			



References: O = OSHA 1926 Subpart CC, 1926.601, 1910.180 A = PCSA #4, ASME B30.5, B30.10

Status: ✓ = Satisfactory X = Safety Hazard M = Monitor N/A = Not Applicable

O-1926.1413		168.		Wire Rope							
Rope Application	Type	Size	Construct.	Grade	Core	Rope Damage	Measured Wear	Broken Wires	Lubrication	End Connections	Status
Main Hoist Drum	RLAL	1"	6X29	EIPS	1WTL	✓	✓	✓	12-16-17 ✓	✓	✓
Aux. Hoist Drum	RRL	7/8"	6X29	EIPS	1WTL	✓	✓	✓	✓	✓	✓
Boom Hoist Drum	RLAL	3/4"	6X29	EIPS	1WTL	✓	✓	✓	12-16-17 ✓	✓	✓
Boom Pendants	RRL	1 1/16"	6X19	EIPS	1WTL	✓	✓	✓	12-16-17 ✓	✓	✓
Jib Pendants	RRL	7/8"	6X19	EIPS	1WTL	✓	✓	✓	✓	✓	✓
Other											

Main Load Block & Hook		
Manufacturer:	MCKISSICK S/N 635980	
Rated Capacity:	25 TONS	
Block Weight:	435 lbs	
Hook Tram Meas:	5"	
REFERENCE	ITEM	Status
O-1926.1433 (d)(3)	169. Capacity Marking	✓
O-1926.1433 (d)(3)	170. Weight Marking	✓
O-1926.1412 (f)(2)(iii)	171. Sheave(s)	✓
O-1926.1433 (d)(4)	172. Safety Latches	✓
A-B30.10-2.10.5 (f)	173. 0° Hook Bend or Twist	✓
A-B30.10-2.10.5 (g)	174. 5% Hook Opening or 1/4" Max.	✓
A-B30.10-2.10.5 (e)	175. 10% Hook Wear Max.	✓
O-1926.1412 (f)(2)(iii)	176. Swivel	✓
O-1926.1412 (f)(2)(iii)	177. Bearing	✓
O-1926.1413 (a)(2)(i)(D)	178. Wedge Socket / End Fitting	✓
O-1926.1412 (d)(1)(vi)	179. Reeving	✓
A-B30.5-2.1.3 (i)	180. NDT Results:	
	181. Other	

Overhaul Ball & Hook		
Manufacturer:	JOHNSON S/N 07-865	
Rated Capacity:	15 TONS	
Block Weight:	713 lbs	
Hook Tram Meas:	5 1/2"	
REFERENCE	ITEM	Status
O-1926.1433 (d)(3)	182. Capacity Marking	✓
O-1926.1433 (d)(3)	183. Weight Marking	✓
O-1926.1433 (d)(4)	184. Safety Latches	✓
A-B30.10-2.10.5 (f)	185. 0° Hook Bend or Twist	✓
A-B30.10-2.10.5 (g)	186. 5% Hook Opening or 1/4" Max.	✓
A-B30.10-2.10.5 (e)	187. 10% Hook Wear Max.	✓
O-1926.1412 (f)(2)(iii)	188. Swivel	✓
O-1926.1412 (f)(2)(iii)	189. Bearing	✓
O-1926.1413 (a)(2)(i)(D)	190. Wedge Socket / End Fitting	✓
A-B30.5-2.1.3 (i)	191. NDT Results:	
	192. Other	

### No-Load Operational Test

REFERENCE	ITEM	Status	Caution: Operation of cranes by Inspectors is limited to those crane functions necessary to accomplish the inspection. Inspectors must meet operator trainee qualification requirements in ASME B30.5 and only operated under the direct supervision of a certified operator.
O-1926.1412 (f)(3)	193. No-Load Operational Test	✓	

A-B30.5-2.2.2

194.

### Load Test

Hoisting from:	Boom / Jib Length	Load Radius	Boom Angle	Parts of Line	Rated Capacity	Test Weight	% of Rated Capacity
Boom							
Jib							

Results of Load Test ☐ Passed ☐ Failed ☒ Not Applicable  
Explanation:

Caution: Load Test shall be conducted by a qualified person. Operators must be certified through a nationally accredited and OSHA recognized certification program, such as CIC.



## Deficiency Report

craneinstitute.com • 3880 St. Johns Parkway • Sanford, FL 32771 • 1-800-832-2726

Date:	Owner:	Mfg:	SN:
-------	--------	------	-----

The following corrective action(s) (repairs, adjustments, replacement parts, etc.) are to be performed by a qualified person in accordance with all the manufacturer's instructions, specifications, and requirements. OSHA requires that if any deficiency is identified as a safety hazard (X), the equipment must be taken out of service until it has been corrected.

If the qualified person determines that though not presently a safety hazard, the deficiency needs to be monitored (M), the employer must ensure that the deficiency is checked in the monthly inspections.


X = Safety Hazard      M = Monitor

[illegible]

Inspector: \_\_\_\_\_

Company Representative: \_\_\_\_\_

Trinity/Quenlan



518-921-0269

Started

1-22-19

## Critical Lift Worksheet

*critical lift*  
*Plan of Correspondence*

Title: \_\_\_\_\_ Date: 1/15/2018  
 Project: Steel Erection Job Number: \_\_\_\_\_  
 Description: ST Pete Job  
 Jobsite Address: \_\_\_\_\_  
 Customer: Trinity P.O./Contract#: \_\_\_\_\_  
 Lift Plan Drawing and Load Placement Drawing attached? Yes No  
 Notes: \_\_\_\_\_

## Crane Information

Manufacturer: Terex Crane Radius: 80 ft  
 Model: HC 110 Crane Capacity at Radius: 11,260 lbs  
 Serial #: \_\_\_\_\_ Capacity at Pick Point: \_\_\_\_\_  
 Crane Rating: 110 t Capacity at Set Point: \_\_\_\_\_  
 Crane Inspection Date: \_\_\_\_\_ Notes: \_\_\_\_\_  
 Notes: \_\_\_\_\_

## Lift Information

## Crane Configuration

Crane Carrier: On Extended Crawlers  
 Counterweight: 52,900 Counterweight  
 Chart Capacity: 11,260 lbs  
 Main Boom Length: 200' 59HI Offset Tip Boom  
 Boom Sections: \_\_\_\_\_  
 Parts of Line: \_\_\_\_\_  
 Line Size: \_\_\_\_\_  
 Capacity of Line @ Parts: \_\_\_\_\_  
 Radius: 80 ft  
 Boom Angle: 78.6°  
 Tip Height: 253.2 ft  
 Jib Used? Yes No  
 Jib: 60' #9HL Jib  
 Jib Offset: 25°  
 Jib Angle from Ground: 53.6°  
 Crawler Load: 559 psf heel, 2,696 psf toe  
 17.9' track bearing length, at 180° Swing Angle


## Load Configuration

Net Load Weight: 10,645 lbs  
 Description: \_\_\_\_\_  
 Dimensions: \_\_\_\_\_  
 Load Weight: 10,645 lbs  
 Rigging Weight: 0 lbs  
 Hook Weight: 0 lbs  
 Block Weight: 0 lbs  
 Load Line Weight: 0 lbs  
 Hook Height: 123 ft  
 Sling Length: \_\_\_\_\_  
 Sling Angle: \_\_\_\_\_  
 Sling Equipment #: \_\_\_\_\_  
 Sling Type: \_\_\_\_\_  
 Spreader Bar #: \_\_\_\_\_  
 Spreader Bar Capacity: \_\_\_\_\_  
 Hook Block: \_\_\_\_\_  
 Shackle Type: \_\_\_\_\_  
 Shackle Qty: \_\_\_\_\_  
 Shackle Capacity: \_\_\_\_\_  
 Additional Rigging: 0 lbs  
 Additional Rigging Capacity: \_\_\_\_\_  
 % of Chart Capacity: 95%  
 Chart Capacity Deduction: \_\_\_\_\_  
 Deduct Capacity: \_\_\_\_\_  
 Notes: \_\_\_\_\_

## Setup Information

Crane Setup: Over Rear 360° Over Front Over Side  
 Setup Distance: \_\_\_\_\_  
 Mat Used? Yes No  
 Mat Dimensions: \_\_\_\_\_  
 Ground Bearing Pressure below Mat: \_\_\_\_\_  
 Notes: \_\_\_\_\_





# Load Chart

Project  
Customer  
Description

## Terex HC 110

Boom: 59HI Offset Tip Boom  
Jib: #9HL Jib  
Base: On Extended Crawlers  
Counterweight: 52,900 Counterweight  
Range: 360°  
Capacity: 75%  
Chart ID: HC-110\_CR-59HI

Boom Length (ft)	Boom Angle	Jib Length (ft)	Jib Offset	Tip Height (ft)	Lift Radius (ft)	Capacity (lbs)	Note
200	80.7°	60	25°	260.6	70	11,330	1
200	78.4°	60	25°	257.8	80	11,260	1
200	76.1°	60	25°	254.6	90	10,980	1
200	73.7°	60	25°	250.9	100	10,710	1
200	71.3°	60	25°	246.7	110	9,670	
200	68.8°	60	25°	242.1	120	8,250	
200	66.3°	60	25°	236.9	130	7,080	
200	63.7°	60	25°	231.1	140	6,080	
200	61°	60	25°	224.8	150	5,220	
200	58.3°	60	25°	217.8	160	4,470	
200	55.4°	60	25°	210	170	3,820	
200	52.5°	60	25°	201.5	180	3,240	
200	49.3°	60	25°	192	190	2,740	
200	46°	60	25°	181.4	200	2,280	

This data is for reference use only. Operator must refer to in-cab charts to determine allowable lifting capacities.

## Justin Perrino

---

**From:** Damon Westfall <DamonWestfall@trinityfabricators.com>  
**Sent:** Saturday, January 20, 2018 9:24 AM  
**To:** Justin Perrino  
**Cc:** Wes Stevens; John Quinlan; Bill Champ; Mike Wilson; Jody Brown; Marc Reeves  
**Subject:** RE: Revised Lift Plan

I apologize for the way the lifting plan was handled – I agree it was not executed properly. I was told that John Quinlan (the owner of the erection firm) had communicated his plan and provided the revised loading chart prior to picking the beams, but I should have verified that with you prior to hoisting them – Again, I apologize for that. Trinity and Quinlan are very much focused on safety, and I assure you this will not happen again.

Damon Westfall



o. 904-284-9657 ext. 103  
c. 904-219-1712  
f. 904-284-9750  
825 Corporate Square Road  
Green Cove Springs, Florida 32043

**From:** Justin Perrino [mailto:jperrino@ajaxbuilding.com]  
**Sent:** Friday, January 19, 2018 3:24 PM  
**To:** Damon Westfall <DamonWestfall@trinityfabricators.com>  
**Cc:** Wes Stevens <wstevens@ajaxbuilding.com>; John Quinlan <johnhquinlan@yahoo.com>; Bill Champ <bchamp@ajaxbuilding.com>; Mike Wilson <mwilson@ajaxbuilding.com>; Jody Brown <jbrown@ajaxbuilding.com>; Marc Reeves <Marc@ajaxbuilding.com>  
**Subject:** RE: Revised Lift Plan

Attached load chart was received after the pick was made.  
It indicates the required capacity with the jib angle reduced.

Apparently it was a mistake that it wasn't sent to us but regardless Trinity/Quinlan knew to get our acknowledgement before making the pick. This lift plan has been very poorly executed and we expect better especially when it comes to safety. I'm not sure how the pick would have been made if Ajax wasn't pushing the issue.

We need confirmation that Trinity/Quinlan is focused on safety as the number one priority and following Ajax direction.

**From:** Justin Perrino  
**Sent:** Friday, January 19, 2018 9:01 AM

**To:** Marc Reeves <[Marc@ajaxbuilding.com](mailto:Marc@ajaxbuilding.com)>; Jody Brown <[jbrown@ajaxbuilding.com](mailto:jbrown@ajaxbuilding.com)>; Damon Westfall <[DamonWestfall@trinityfabricators.com](mailto:DamonWestfall@trinityfabricators.com)>  
**Cc:** Wes Stevens <[wstevens@ajaxbuilding.com](mailto:wstevens@ajaxbuilding.com)>; John Quinlan <[johnhquinlan@yahoo.com](mailto:johnhquinlan@yahoo.com)>; Bill Champ <[bchamp@ajaxbuilding.com](mailto:bchamp@ajaxbuilding.com)>  
**Subject:** RE: Revised Lift Plan  
**Importance:** High

Damon

Trinity/Quinlan is not permitted to lift anything over the weight permitted on the lifting plan submitted. We are supposed to be getting a revised lifting plan to account for the heavier beam noted below. Weight of rigging needs to be clearly noted an accurate and accounted for.

**From:** Marc Reeves  
**Sent:** Wednesday, January 17, 2018 2:16 PM  
**To:** Jody Brown <[jbrown@ajaxbuilding.com](mailto:jbrown@ajaxbuilding.com)>; Damon Westfall <[DamonWestfall@trinityfabricators.com](mailto:DamonWestfall@trinityfabricators.com)>; Justin Perrino <[jperrino@ajaxbuilding.com](mailto:jperrino@ajaxbuilding.com)>  
**Cc:** Wes Stevens <[wstevens@ajaxbuilding.com](mailto:wstevens@ajaxbuilding.com)>; John Quinlan <[johnhquinlan@yahoo.com](mailto:johnhquinlan@yahoo.com)>; Bill Champ <[bchamp@ajaxbuilding.com](mailto:bchamp@ajaxbuilding.com)>  
**Subject:** RE: Revised Lift Plan

11335 is 690lbs more than the lift plan that was provided shows and exceeds (by 5lbs) the load chart capacity at 70' radius. I'm assuming these numbers do not include the rigging / block / load line weight?

*Marc Reeves, CRIS*  
Director of Risk Management



1080 Commerce Blvd.  
Midway, FL 32343  
Phone: 850-224-9571  
Fax: 850-224-2496

**From:** Jody Brown  
**Sent:** Wednesday, January 17, 2018 2:09 PM  
**To:** Damon Westfall <[DamonWestfall@trinityfabricators.com](mailto:DamonWestfall@trinityfabricators.com)>; Justin Perrino <[jperrino@ajaxbuilding.com](mailto:jperrino@ajaxbuilding.com)>  
**Cc:** Wes Stevens <[wstevens@ajaxbuilding.com](mailto:wstevens@ajaxbuilding.com)>; John Quinlan <[johnhquinlan@yahoo.com](mailto:johnhquinlan@yahoo.com)>; Bill Champ <[bchamp@ajaxbuilding.com](mailto:bchamp@ajaxbuilding.com)>; Marc Reeves <[Marc@ajaxbuilding.com](mailto:Marc@ajaxbuilding.com)>  
**Subject:** RE: Revised Lift Plan

All,



*\* Crane jib collapse  
Incident*

### SUPERVISOR'S INCIDENT INVESTIGATION REPORT

**Project Name:** St. Petersburg Police Headquarters **Project Number:** 201522

**Superintendent's Name:** Jody Brown (report by Bryan Marlow) **Date:** 1/31/18 **Time:** 3:00 PM

**Where Incident Occurred:** North of the admin building on the site about 70 west of the annex building.

**Company's Name and Address involved in incident:** Quinlan Erectors, subcontractor for Trinity Steel

**Company's Superintendent/Forman/Contact:** Allan Hensley. 407-779-6532

**Description of Incident:** See attached discription

**Witnesses: (attach statements as necessary)** No immediate eye witnesses however incident can be viewed by the project webcam.

**Unsafe condition or act causing incident:** None. Inspection was made at the start of the work shift and Anti Locking device was functioning according to operator Ray-Paul Rougeau.

**Was there equipment malfunction?** ☒ Yes ☐ No

**Action taken or to be taken to prevent similar incidents:** Investigation still on going

**Other information concerning this incident, which doesn't fit into spaces above:** Statement of operator given to Ajax with questions from Ajax to operator.

**Follow up action by the Safety Director:** \_\_\_\_\_

**Did an Injury occur during this Incident?** ☐ Yes ☒ No

(If yes fill out supervisor's accident investigation report (form #47) and attach to this report.)

xc: Human Resources (original), Safety Director, VP of Operations, Director of Operations, Operations Manager, Sr. Project Manager

01/25/2011

Forms  
Adminis  
trator

Digitally signed by  
Adminis  
trator  
DN: cn=Forms,  
ou=Engineering,  
o=Quinlan Erectors,  
c=US  
Date: 2011.01.24 13:03:02  
+05'00'


Description of Incident:

The crane operator was moving the crane location when the head ache ball retracted into the jib causing the approximately 35' section of the jib to snap off of the main boom of the crane and hang from the cable. No load was being picked at the time. The "anti tube locking device" apparently malfunctioned because it did not cause the cable to stop before the head ache ball retracted into the jib. In addition the crane operator thought that the cable was not engaged however the cable lever must have not being fully locked into the disengaged position causing the cable to continue to retract. There was no injuries or damage to the project or property with the exception of the crane boom suffering significant damage.

As I (Ray-Paul Rougeau) finished my lift on one section of the building, I then proceeded to set the crane up to be tracked to a new location. Set the boom at safe angle and hoisted to a safe position for travel. As I then began traveling about 15 to 20 ft, I was watching the tracks because I thought they were binding. Then I heard a loud pop and wood debris was hitting the ground around me from the jib. ~~My~~ Immediately stopped all operations and locked down the crane.

Once quickly assessed lowered the crane boom to the ground as quickly and safely as possible to prevent any further damage or risk.

Ray-Paul Rougeau



Here One Week.

1/31/18

Quinlan Enterprise

No distractions

When lock was working this morning  
Boom Facing North  
SAFE POSITION means Boom angle  
Operator thought Cable was not engaged.  
Main Hoist Line Break was engaged.  
4 years experience  
3 months experience on that model Crane  
No Talking on Phone  
No Music  
Under No influence of Alc. or Drugs  
Not Swinging the Boom

Hoist Line ~~Brake~~ Brakes & Cable Hoist lever  
are 2 different items. Line Brake is a  
Pedals Pedal has to be disengaged for  
Hoist Cable to operate



704 miles R/T



# OSHA / ASME ANNUAL/PERIODIC INSPECTION CHECKLIST

## Lattice Boom Crane

craneinstitute.com • 3880 St. Johns Parkway • Sanford, FL 32771 • 1-800-832-2726

Owner: <b>QUINLAN Enterprises</b>	Contact Person: <b>JOHN QUINLAN</b>	Date: <b>2-6-18</b>
Location: <b>ST. PETERSBURG, FL</b>	Service Status: <b>Annual</b>	Hours: <b>6471 (CAB)</b>
Make: <b>TEREX</b>	Model: <b>HC-110</b>	Serial Number: <b>AC 4173</b>
Unit ID:	Max. Capacity: <b>110 TONS</b>	Inspector: <b>R. Gardner</b>

Before inspecting crane, lock out/tag out power source.

Consult operator/service manual, service bulletins, etc. for additional inspection items.

Before inspection, crane must be set up away from personnel and power lines, with outriggers/crawlers fully extended and crane leveled on firm ground.

OSHA and ASME allow only qualified and competent persons to inspect cranes. To qualify, inspectors must have been through training, have extensive knowledge and demonstrated ability.

References: O = OSHA 1926 Subpart CC, 1926.601, 1910.180 A = PCSA #4, ASME B30.5, B30.10

Status: ✓ = Satisfactory X = Safety Hazard M = Monitor N/A = Not Applicable

REFERENCE	ITEM	Status	REFERENCE	ITEM	Status
<b>Historical Data</b>			<b>Carrier Power Plant (Lower)</b>		
O-1926.1412 (e)(3)	1. Monthly Inspection Records	✓	O-1926.1412 (f)(2)(vi)	34. Performance	NA
A-B30.5-2.3.1 (a)	2. Maintenance Records	✓	O-1926.1433 (d)(9)	35. Exhaust System / Guards & Insulators	
O-1926.1434 (a)	3. Modification Records	NA	O-1926.1433 (d)(8)	36. Belts	
A-B30.5-2.2.2 (b)	4. Load Test Records	NA	O-1926.1433 (d)(8)	37. Guards / Covers / Rotat. & Recip. Parts	
O-1926.1412 (f)(7)	5. Annual Inspection Record	✓		38. Other	
<b>General</b>			<b>Carrier</b>		
A-B30.5-2.1.3 (a)	6. Sheet Metal	✓	O-1926.601 (b)(14)	39. Transmission	
O-1926.1433 (d)(8)	7. Guards / Covers	✓	O-1926.601 (b)(14)	40. Drive Line	
O-1926.601(2)(i)&(ii)	8. External Lights	✓	O-1926.1412 (f)(2)(ix)	41. Tires	
A-B30.5-3.4.7	9. Housekeeping	✓	O-1926.1412 (f)(2)(i)	42. Main Frame Members	
O-1926.1433 (d)(5)	10. Safety / Warning Decals & Labels	✓	O-1926.1412 (f)(2)(x)	43. Hydraulic Hoses / Tubing / Fittings	
O-1926.1422	11. Hand Signal Chart	✓	O-1926.1412 (d)(1)(iv)	44. Hydraulic Fluid Level	
	12. Other		O-1926.1423 (c)(3)(ii)	45. Anti-Skid Surface	
	13. Other		O-1926.1417 (aa)	46. Front Bumper Counterweight	
<b>Driver's Cab &amp; Station</b>				47. Other	
O-1926.601 (b)(1)	14. Service Brake	NA	<b>Outriggers</b>		
O-1926.601 (b)(1)	15. Emergency Brake		O-1926.1412 (f)(2)(i)	48. Boxes	
O-1926.601 (b)(1)	16. Parking Brake		O-1926.1412 (f)(2)(i)	49. Beams	
O-1926.601 (b)(2)	17. Headlights		O-1926.1412 (f)(2)(xiii)	50. Cylinders	
O-1926.601 (b)(2)	18. Taillights		O-1926.1412 (f)(2)(xiv)	51. Floats / Pads	
O-1926.601 (b)(2)(ii)	19. Brake Lights		O-1926.1412 (f)(2)(x)	52. Hydraulic Hoses / Tubes / Fittings	
O-1926.601 (b)(3)	20. Audible Warning Device		O-1926.1412 (f)(2)(xii)	53. Holding Valves	
O-1926.601 (b)(4)(i)	21. Backup Audible Alarm		O-1926.1412 (f)(2)(iii)	54. Position Locks	
O-1926.1433 (d)(7)(iii)	22. Windows		O-1926.1433 (d)(5)	55. Warning Signs	
O-1926.601 (b)(5)	23. Windshield Wipers			56. Other	
O-1926.601 (b)(5)	24. Defroster		<b>Crawler Assembly</b>		
O-1926.601 (b)(6)	25. Overhead Protection		O-1926.1412 (f)(2)(i)	57. Car Body / Side Frames	✓
O-1926.601 (b)(7)	26. Housekeeping		O-1926.1412 (f)(2)(vii)	58. Chain - Condition / Adjustment	✓
O-1926.1412(f)(2)(xviii)&(xix)	27. Seat		O-1926.1412 (f)(2)(vii)	59. Sprockets / Idlers / Rollers	✓
O-1926.601 (b)(9)	28. Seat Belts		O-1926.1412 (f)(2)(i)	60. Track Pads / Pins	✓
O-1926.601 (b)(14)	29. Tires		O-1926.1412 (f)(2)(viii)	61. Travel Locks	✓
O-1926.601 (b)(14)	30. Steering Mechanism		O-1926.1412 (f)(2)(viii)	62. Steering Clutches	✓
O-1926.601 (b)(14)	31. Operating Controls			63. Other	
O-1926.601 (b)(14)	32. Safety Devices				
O-1926.601 (b)(14)	33. Fire Extinguisher				

References: O = OSHA 1926 Subpart CC, 1926.601, 1910.180 A = PCSA #4, ASME B30.5, B30.10

Status: ✓ = Satisfactory X = Safety Hazard M = Monitor N/A = Not Applicable

REFERENCE	ITEM	Status	REFERENCE	ITEM	Status
<b>Operator's Cab &amp; Station</b>			<b>Rotating Upper Structure (continued)</b>		
O-1926.1412 (f)(2)(xxi)	64. Grab Rails / Steps / Platforms	✓	O-1926.1412 (f)(2)(iv)	116. Main Hoist – Clutches / Brakes	✓
O-1926.1423 (c)(3)(ii)	65. Anti-Skid Surface	✓	O-1926.1412 (d)(1)(vi)	117. Main Hoist – Rope Spooling	✓
O-1926.1433 (d)(7)(iii)	66. Windows	✓	O-1926.1413 (a)(4)(i)(B)	118. Main Hoist – Minimum (2) rope wraps	✓
O-1926.1433 (d)(7)(iii)	67. Windshield Wiper(s)	✓	O-1926.1412 (f)(2)(iv)	119. Aux. Hoist – Clutches / Brakes	✓
O-1926.1433 (d)(7)(ii)	68. Door Restraint	✓	O-1926.1412 (d)(1)(vi)	120. Aux. Hoist – Rope Spooling	✓
O-1926.1433 (d)(6)	69. Fire Extinguisher	✓	O-1926.1413 (a)(4)(i)(B)	121. Aux. Hoist – Minimum (2) rope wraps	✓
O-1926.601 (b)(4)	70. Mirrors	✓	O-1926.1412 (f)(2)(iv)	122. Boom Hoist – Clutches / Brakes	✓
O-1926.1412 (f)(2)(xvii)&(xix)	71. Seat	✓	O-1926.1412 (d)(1)(vi)	123. Boom Hoist – Rope Spooling	✓
A-B30.5-1.8.1 (e)	72. Seat Belts	✓	O-1926.1413 (a)(4)(i)(B)	124. Boom Hoist – Minimum (2) rope wraps	✓
O-1926.1433 (d)(1)	73. Operator's Manual	✓	O-1926.1412 (f)(2)(iv)	125. Boom Hoist – Clutch / Pawls / Ratchets	✓
O-1926.1433 (d)(5)	74. Decals	✓	O-1926.1412 (f)(2)(xi)	126. Swing System / Assembly	✓
O-1926.1407 (g)	75. Electrocution Warning Sign (Inside)	✓	O-1926.1412 (f)(2)(xi)	127. Hydraulic Motors / Valves / Lines / Etc.	✓
O-1926.1422	76. Hand Signal Chart	✓	O-1926.1412 (f)(2)(ii)	128. Drums / Flanges	✓
O-1926.1412 (f)(2)(iv)	77. Swing Brake	✓	O-1926.1412 (f)(2)(iv)	129. Clutch / Brake Protection	✓
O-1926.1412 (f)(2)(iii)	78. Positive Swing Lock	✓	O-1926.1412 (f)(2)(iii)	130. Torque Converter	✓
O-1926.1412 (d)(i)&(ii)	79. Control Function	✓	O-1926.1423 (c)(3)(ii)	131. Anti-Skid Surface	✓
O-1926.1412 (f)(2)(xi)(A)	80. Air Pressure	NA	O-1926.1412 (f)(2)(xxi)	132. Steps / Hand Holds / Platforms	✓
O-1926.1415 (a)(4)	81. Foot Brakes – Latches / Linkage	✓	O-1926.1412 (f)(2)(xx)&(xxi)	133. Access to Cab and Roof	✓
O-1926.1412 (f)(2)(iv)	82. Engine Clutch	✓	O-1926.1412 (f)(2)(x)&(xi)	134. Air System – Compressor / Lines / Etc.	NA
O-1926.1412 (d)(i)&(ii)	83. Accelerator / Throttle Control	✓	O-1926.1412 (f)(2)(i)(B)	135. Counterweight Mounting	✓
O-B30.5-1:6.1 (a)	84. Control Marking	✓	O-1926.1433 (d)(5)	136. Counterweight Warning Sign	✓
<b>Load Chart</b>			O-1926.1407 (g)	137. Electrocution Warning Sign (Outside)	✓
O-1926.1433 (d)(1)	85. Per Configuration	✓		138. Other	
O-1910.180 (c)(2)	86. Durable	✓	<b>Boom Support System</b>		
O-1910.180 (c)(2)	87. Legible	✓	O-1926.1412 (f)(2)(i)	139. Gantry / Mast	✓
O-1910.180 (c)(2)	88. Visible From Operator's Station	✓	O-1926.1415 (a)(2)	140. Boom Stops	✓
O-1910.180 (c)(2)	89. Secured	✓	O-1926.1412 (f)(2)(ii)&(iii)	141. Inner Bail	✓
	90. Other	✓	O-1926.1412 (f)(2)(ii)&(iii)	142. Outer Bail / Equalizer	✓
<b>Safety Devices / Operational Aids</b>			O-1926.1412 (f)(2)(ii)	143. Sheave(s)	✓
O-1926.1415 (a)(7)	91. Horn	✓	O-1926.1412 (d)(1)(vi)	144. Boom Hoist Reeving	✓
O-1926.1416 (e)(1)	92. Boom Angle Indicator	✓		145. Other	
O-1926.1416 (e)(5)(ii)	93. Main Drum Rotation Indicator	✓	<b>Boom</b>		
O-1926.1416 (e)(5)(ii)	94. Auxiliary Drum Rotation Indicator	✓	O-1926.1412 (f)(2)(xvii)	146. Boom Section Identification	✓
O-1926.1412 (f)(2)(v)	95. Load Moment Indicator	✓	O-1926.1404 (m)	147. Boom Section Sequence	✓
O-1926.1416 (e)(4)	96. Load Weight Indicator	✓	O-1926.1404 (m)	148. Boom Section Alignment	✓
O-1926.1416 (e)(1)	97. Radius Indicator	✓	O-1926.1412 (f)(2)(xvii)	149. Warning Decals	✓
O-1926.1415 (a)(1)	98. Crane Level Indicator	✓	O-1926.1412 (f)(2)(i)	150. Spreader Bar	✓
O-1926.1416 (d)(3)	99. Anti-Two Block Device	✓	O-1926.1412 (f)(2)(ii)&(iii)	151. Sheave(s)	✓
O-1926.1416 (d)(1)	100. Boom Hoist Limiting Device	✓	O-1926.1413 (a)(2)(i)(D)	152. Hoist Line Dead End	✓
O-1926.1412 (f)(2)(iv)	101. Boom Hoist Ratchet and Pawl	✓	O-1926.1412 (a)(2)(i)(D)	153. Wire Rope Retainer(s)	✓
O-1926.1416 (e)(5)(i)	102. Outrigger / Stabilizer Position Sensor	NA	O-1926.1412 (f)(2)(iii)	154. Boom Foot Pins / Keepers	✓
O-1926.1416 (e)(2)	103. Luffing Jib Angle Indicator	NA	O-1926.1412 (f)(2)(i)	155. Boom Head Section	✓
<b>Power Plant (Upper)</b>			O-1926.1412 (f)(2)(i)	156. Auxiliary Boom Head	NA
O-1926.1412 (f)(2)(vi)	104. Performance	✓	O-1926.1412 (f)(2)(i)	157. Lattice Members	✓
O-1926.1433 (d)(9)	105. Exhaust System / Guards & Insulators	✓	O-1926.1412 (f)(2)(i)	158. Cord Members	✓
O-1926.1412 (d)(1)(iii)	106. Hoses	✓	O-1926.1412 (f)(2)(i)	159. End Connections / Pins	✓
O-1926.1433 (d)(8)	107. Guards / Covers / Rotat. & Recip. Parts	✓		160. Other	
	108. Other	✓	<b>Jib</b>		
<b>Rotating Upper Structure</b>			O-1926.1415 (a)(3)	161. Stops	✓
O-1926.1412 (f)(2)(iii)	109. Turntable / Bearing	✓	O-1926.1412 (f)(2)(ii)	162. Sheave(s)	✓
O-1926.1412 (f)(2)(iii)	110. Turntable – Rollers / Roller Path	✓	O-1926.1413 (a)(2)(i)(D)	163. Wire Rope Retainer(s)	✓
O-1926.1412 (f)(2)(iii)	111. Ring Gear / Pinion Gear	✓	O-1926.1412 (f)(2)(i)	164. Lattice Members	✓
O-1926.1412 (f)(2)(xi)	112. Hydraulic Pump(s)	✓	O-1926.1412 (f)(2)(i)	165. Cord Members	✓
O-1926.1412 (f)(2)(x)	113. Hydraulic Hoses / Tubing / Fittings	✓	O-1926.1412 (f)(2)(i)	166. End Connections / Pins	✓
O-1926.1412 (f)(2)(xi)	114. Hydraulic Pressure	✓	O-1926.1416 (d)(2)	167. Luffing Jib Stops	✓
O-1926.1412 (d)(1)(viii)	115. Electrical Wiring	✓			

References: O = OSHA 1926 Subpart CC, 1926.601, 1910.180 A = PCSA #4, ASME B30.5, B30.10

Status: ✓ = Satisfactory X = Safety Hazard M = Monitor N/A = Not Applicable

O-1926.1413 168.		<b>Wire Rope (New) 2-6-18</b>									
Rope Application	Type	Size	Construct.	Grade	Core	Rope Damage	Measured Wear	Broken Wires	Lubrication	End Connections	Status
Main Hoist Drum	RRL	1"	6X37	EIP	1WRL	✓	✓	✓	✓	✓	NEW 2-6-18
Aux. Hoist Drum	RRL	7/8"	6X29	EIPS	1WRL	✓	✓	✓	✓	✓	✓
Boom Hoist Drum	RLAL	3/4"	6X29	EIPS	1WRL	✓	✓	✓	✓	✓	✓
Boom Pendants	RRL	1 1/16"	6X19	EIPS	1WRL	✓	✓	✓	✓	✓	✓
Jib Pendants	RRL	7/8"	6X19	EIPS	1WRL	✓	✓	✓	✓	✓	✓
Other	(All wire rope lubricated ON 2-6-18)										

Main Load Block & Hook		
Manufacturer:	McKissick S/N 635980	
Rated Capacity:	25 TONS	
Block Weight:	435 lbs	
Hook Tram Meas:	5"	
REFERENCE	ITEM	Status
O-1926.1433 (d)(3)	169. Capacity Marking	✓
O-1926.1433 (d)(3)	170. Weight Marking	✓
O-1926.1412 (f)(2)(ii)	171. Sheave(s)	✓
O-1926.1433 (d)(4)	172. Safety Latches	✓
A-B30.10-2.10.5 (f)	173. 0° Hook Bend or Twist	✓
A-B30.10-2.10.5 (g)	174. 5% Hook Opening or 1/4" Max.	✓
A-B30.10-2.10.5 (e)	175. 10% Hook Wear Max.	✓
O-1926.1412 (f)(2)(iii)	176. Swivel	✓
O-1926.1412 (f)(2)(iii)	177. Bearing	✓
O-1926.1413 (a)(2)(i)(D)	178. Wedge Socket / End Fitting	✓
O-1926.1412 (d)(1)(vi)	179. Reeving	✓
A-B30.5-2.1.3 (i)	180. NDT Results:	
	181. Other	

Overhaul Ball & Hook		
Manufacturer:	Johnson S/N 07-865	
Rated Capacity:	15 TONS	
Block Weight:	713 lbs	
Hook Tram Meas:	5 1/2"	
REFERENCE	ITEM	Status
O-1926.1433 (d)(3)	182. Capacity Marking	✓
O-1926.1433 (d)(3)	183. Weight Marking	✓
O-1926.1433 (d)(4)	184. Safety Latches	✓
A-B30.10-2.10.5 (f)	185. 0° Hook Bend or Twist	✓
A-B30.10-2.10.5 (g)	186. 5% Hook Opening or 1/4" Max.	✓
A-B30.10-2.10.5 (e)	187. 10% Hook Wear Max.	✓
O-1926.1412 (f)(2)(iii)	188. Swivel	✓
O-1926.1412 (f)(2)(iii)	189. Bearing	✓
O-1926.1413 (a)(2)(i)(D)	190. Wedge Socket / End Fitting	✓
A-B30.5-2.1.3 (i)	191. NDT Results:	
	192. Other	

### No-Load Operational Test

REFERENCE	ITEM	Status	Caution: Operation of cranes by inspectors is limited to those crane functions necessary to accomplish the inspection. Inspectors must meet operator trainee qualification requirements in ASME B30.5 and only operated under the direct supervision of a certified operator.
O-1926.1412 (f)(3)	193. No-Load Operational Test	✓	

A-B30.5-2.2.2 194.		Load Test					
Hoisting from:	Boom / Jib Length	Load Radius	Boom Angle	Parts of Line	Rated Capacity	Test Weight	% of Rated Capacity
Boom							
Jib							

Results of Load Test ☐ Passed ☐ Failed ☒ Not Applicable



Explanation:

Cautions: Load Test shall be conducted by a qualified person. Operators must be certified through a nationally accredited and OSHA recognized certification program, such as CIC.





*Crane operator certification*





68°



[www.verifycco.org](http://www.verifycco.org): Verify CCO Online (VCO)



IFIED

000000R

IONS:

BTF STC, TWR,  
DDO, DPD

ERATOR

TS: 0631/2020

*Michael F. Quinlan*  
on J-Point, Chief Erector/Operator, NCCCO  
License # 0631/2020

ation of Crane Operators

ation of Crane Operators

ation of Crane Operators

ation of Crane Operators

rtification of Crane

ed CCO cards for

Crane Inspectors and Lift

MICHAEL F. QUINLAN

✓ CCO Certified

### Operator Certifications

Certification Number: R101059325

Expiration Date: 10/31/2020

#### Designations Held:

- Lattice Boom Crawler Cranes (LBC)
- Lattice Boom Truck Cranes (LBT)
- Telescopic Boom Cranes - Swing Cab (TLL)



February 9, 2018

Quinlan Enterprises  
514 Mary Lee Street  
Claxton, GA 30417  
Attention: John Quinlan

RE: St Petersburg Police Headquarters Facility  
Final Safety Warning

John:

This letter is to serve as a notice that a zero tolerance safety policy is now in effect regarding your company's work on the St Petersburg Police Headquarters Project due to the events outlined below:

- Erecting heavy beams without authorization from the contractor's safety director
- Crane jib malfunction on 1/31
- Ironworker walking steel without being tied off on 2/5

If you receive any further safety infractions that are deemed worthy for expulsion by the contractor, you will be forced to leave the jobsite immediately and trinity will be forced to complete your contract with a different erector. All costs associated with completing the project by another erection company will be taken out of your contract. To ensure enough money is left in your contract, in the event you receive another safety infraction, future payments will be made only when major milestones are completed.

Also, Quinlan will need to have a safety supervisor onsite for the remainder of the project whose sole responsibility is policing the ironworkers to ensure proper use of all required safety equipment.

The hope is that there will be no more safety infractions, and that Quinlan will safely and successfully complete this project. However, safety is the top priority and no future infractions will be tolerated.

Please sign below acknowledging you have received this notice and are taking the steps necessary to comply. This notice will become an amendment to our contract dated July 27, 2017.

ERECTOR:

Quinlan Enterprises

BY:

DATE:

*John H. Quinlan*  
*02/10/2018*  
*John H. Quinlan OWNER*  
Print name of signer and title

Trinity Fabricators, Inc.

BY:

DATE:

*[Signature]*  
*2/12/18*  
*Damon Westman VP*  
Print name of signer and title

A Safety Warning on  
Zero tolerance

**Justin Perrino**

**From:** Damon Westfall <DamonWestfall@trinityfabricators.com>  
**Sent:** Monday, February 12, 2018 3:16 PM  
**To:** Mike Wilson  
**Cc:** Dan Westfall; Justin Perrino; Jody Brown  
**Subject:** RE: SPPD | Safety Notice  
**Attachments:** Executed Safety Notice.pdf


Mike,

Please find the executed notice attached for your records.

In talking with John Quinlan this morning, I know that he is pursuing one of Skanska's previous safety officers that lives in the Tampa area which is a positive sign that they are taking this seriously and addressing the issue accordingly.

I also reached out to two erectors to find out their availability. Florida Atlantic had some men available, and Cutting Edge was not an option.

Damon Westfall

 **trinity fabricators inc.**  
825 Corporate Square  
Green Cove Springs, Florida 32043  
o. 904-284-9657 ext. 103 | c. 904-219-1712

**From:** Damon Westfall  
**Sent:** Friday, February 9, 2018 4:40 PM  
**To:** johnhquinlan@yahoo.com  
**Cc:** Dan Westfall <danwestfall@trinityfabricators.com>; Mike Wilson <mwilson@ajaxbuilding.com>; 'Justin Perrino' <jperrino@ajaxbuilding.com>; Jody Brown <jbrown@ajaxbuilding.com>  
**Subject:** SPPD | Safety Notice

John,

Please review, execute and return the attached as soon as possible.

Damon Westfall  
 **trinity fabricators inc.**

825 Corporate Square  
Green Cove Springs, Florida 32043  
o. 904-284-9657 ext. 103 | c. 904-219-1712



picking up scoria lift off off third floor  
off the side of crane. Picked up the scoria lift  
and started booming up then swing to right and continue  
to boom up then started to lower the scoria lift  
then saw the crane coming up, tried to lower  
scoria lift faster so to stop the crane from coming  
over ~~that~~ was in the chost load of scoria lift  
around 3,650 pound and from center of crane to  
load around 60' boom angle

Michael Clements 4-5-18