Specifications For: Venice, FL Venice, FL-F550 TV LAMP P&T 9-13-18

1 FORD F-550 GAS CAB CHASSIS 205" WB 2X4 CHASSIS

1 6.8L V10 Gas Engine

1 6-Speed Automatic Transmission

1 19,500 lb. GVWR

1 205" Wheel Base

1 Cab Air Conditioner

1 AM / FM Radio

1 16' CARGO BOX FOR CAB/CHASSIS

1 LED Light Package Includes Body Clearance and Stop / Tail / Turn

1 Full Width Barn Doors with CAM (Pipe) Locks on Each Door

2 Laminated Steel Lock

1 Kemlite Covering on Inside Rear Doors

1 Back Up Alarm

1 CUES EXCLUSIVE POWER BOOM CRANE WITH LED LIGHTING

Power actuated boom extends and retracts up to 24" at the touch of a button for precise deployment/retrieval placement of the transporter/camera, 750 lb. capacity, Yellow Retrieval Hook, 75' x 5/32" Cable Length, Floor Mounted, 12VDC, Push Button 4-Function Detachable 12' Pendant Control, Powder Coat Finish. High intensity LED lighting to help light up the manhole to assist in deployment/retrieval of the transporter/camera.

1 BACK-UP COLOR CAMERA SYSTEM [CHASSIS]

1 SAFE ENTRY/EXIT BUMPER

- 1 Three (3) Steps Evenly Spaced
- 1 Bottom Step Folds Up for Ground Clearance
- 1 Safety Grab Handle

1 TRANSPORTER/CAMERA LOCKABLE STORAGE COMPARTMENT WITH NOTCH IN REAR DOOR THRESHOLD OF BODY FOR TV CABLE TO PASS THROUGH TO TRANSPORTER STORAGE DRAWER

- 1 Lockable Storage Compartment for Camera and Transporter
- 1 Sliding Drawer
- 1 Notch in rear door threshold of body for TV cable to pass through to transporter storage Drawer

1 KICKPLATE 2 DRAWER ALUMINUM STORAGE

1 TV HIGH CUBE VAN EXTERIOR LIGHTING & CONTROL ROOM - EVOLUTION 3.0 TO INCLUDE:

2 Amber LED Strobe Warning Beacons

2 Adjustable LED Floodlights Rear of Vehicle Area Illumination

Control Room Interior:

- 1 Lonseal Lonplate Flooring
- 1 Kemlite Wall & Ceiling Covering
- 1 Bulkhead Wall With Passage Door From Control Room to Equipment Room
- 1 Tinted Viewing Window in Bulkhead Wall
- 1 Tinted Viewing Window in Bulkhead Door
- 1 Above Desk Control Console with Rack Mount for Electronic Equipment
- 1 Desktop / Work Area
- 1 12V High Intensity LED Light Fixture
- 2 Electrical Outlet with Dual Receptacles
- 1 Fire Extinguisher with Bracket, 10BC Rating
- 1 Operators Chair, Swivel With Casters
- 1 Breaker Box Storage Area with Locking Positive Latch

1 ROOF TOP AIR CONDITIONER, 13,500 BTU WITH HEAT STRIP

1 BENCH SEAT IN CONTROL ROOM

1 CUSHION FOR BENCH SEAT

1 CLOSET IN CONTROL ROOM

1 CURBSIDE DOOR WITH FOLD-DOWN STEPS FOR EVO 3.0

1 TV HI-CUBE VAN EQUIPMENT ROOM INTERIOR - EVOLUTION 3.0 TO INCLUDE:

- 1 Lonseal Lonplate Flooring
- 1 Kemlite Wall & Ceiling Covering
- 1 Electrical Outlet with Dual Receptacles
- 1 12V High Intensity LED Light Fixture
- 1 15 Minute Courtesy Timer Located at Rear Door Area for 12V LED Interior Lights

1 20-GALLON WASHDOWN SYSTEM TO INCLUDE:

- 1 20-Gallon Fresh Water Tank
- 1 Electric Water Pump
- 1 Retractable Hose Reel with 25' Water Hose and Nozzle

1 UPPER AND LOWER STORAGE CABINET IN EQUIPMENT ROOM

- 1 Lower Storage Cabinet / Work Top with Sink and Faucet
- 1 Upper Wall Mounted Storage Cabinet

1 TOOL CHEST, MODULINE, 5 DRAWER

1 ADDITIONAL LIGHTING AND OUTLET

- 1 Light Mounted Above Work Top
- 1 Dual Receptacle Outlet Above Work Top

1 32" REAR FLAT SCREEN MONITOR MOUNTED IN BULKHEAD WALL

- 1 Flat Screen Monitor
- 1 Cable Assembly Video Monitor to Monitor in Control Room
- 1 Electrical Outlet

1 AIR COMPRESSOR ELECTRIC DRIVE 4.0 CFM @100 PSI TO INCLUDE:

- 1 30-Gallon Air Receiver Tank
- 1 Rear Air Chuck
- 1 Retractable Air Hose Reel with 25' Air Hose with Chuck

1 7000 WATT GAS ONAN GENERATOR

- 1 120 Volt 60 HZ 7000 Watt EFI (Electronic Fuel injection) Commercial Grade Generator
- 1 Gasoline Powered
- 1 Electric Start
- 1 Air Cooled
- 1 Generator Remote Start/Stop Cable assembly

1 GENERATOR COMPARTMENT [UNDER CHASSIS MOUNT]

- 1 Generator Storage Compartment with Lockable External Access Door
- 1 Commercial Power Supply Receptacle, 25' Cord, and Plug
- 1 Electrical Supply Center with Circuit Breaker Box
- 1 Commercial power and Generator Power Connectors
- 1 Automatic Power Transfer Switch

1 SYSTEM ENGINEERING PANEL, FOR POWER INFORMATION AND GENERATOR FUNCTIONS, RACK MOUNTED, TO INCLUDE:

- 1 Four Function AC Power Meter displaying Critical Power Information including:
- 1 Voltage
- 1 Hertz
- 1 Amperage
- 1 Active Power (Watts)

- 1 Front panel Selector Switch for two modes of operation:
- 1 Fixed reading
- 1 Continuous Auto-cycling
- 1 Generator Battery Meter to Display Starting and Charging Voltage
- 1 Generator Hour Meter
- 1 Generator Remote Start/Stop Control Switch
- 1 On/Off Switch for Emergency Warning beacons (Switch to Illuminate When On)

1 P&T ZOOM III M/C CAMERA

- 1 Solid State Color Sewer TV Camera
- 1 Pan & Rotate Camera Head, 40:1 Zoom Ratio, 10x Optical Zoom, 4x Digital Zoom
- 1 NTSC Color Standard, 4x Light Integration
- 1 Camera Lighting System for 6" through 72" lines
- 1 Camera Transportation and Storage Case

1 BRASS COMP STEERABLE CAM TRANS, WHEELED -60V

- 1 Steerable Unit Designed to Turn 360 Degrees Within Its Own Radius
- 1 Set of Driven Rubber Wheels to Inspect 6" Pipe
- 1 Two (2) Speed Transmission to Maximize Torque in Large Diameter Pipe with:
- 1 Manual Shifter on Camera Carrier
- 1 Unit Shall Have Forward, Free Wheel, and Power Reverse Capabilities
- 1 All Six (6) Wheel Drive Transporter Assembly to Include:
- 1 Motor & Enclosed Drive Train
- 1 Tip Up Rear Connector

18" RUBBER WHEEL KIT FOR COMPACT TRANSPORTER

1 10-15" RUBBER WHEEL KIT FOR COMPACT TRANSPORTER

16"-15"PIPE SPACER KIT

1 12"-15" PNEUMATIC TIRE KIT FOR COMPACT TRANSPORTER

18" STEEL 10/12 GR WHEEL KIT FOR COMPACT TRANSPORTER

1 1500' CABLE ASSEMBLY, M/C 12PIN METAL

- 1 1500' Gold Multi Conductor Kevlar Fiber Armored Combination TV Transmission / Tow Cable
- 1.450 Diameter
- 1 Metal Splice Chamber with Pigtail
- 1 Cable Strain Relief

1 TV REEL ASSEMBLY, MECHANICAL FOOTAGE FOR SUMMIT .450 CABLE WIAUTO PAYOUT

- 1 Black Thermoplastic Powder Coated Frame
- 1 Power Levelwind & Multi Ratio Manual Transmission
- 1 Automatic Cable Payout System
- 1 Footage Meter with Local Counter and Remote Counter
- 1 Transmission Control at Viewing Station
- 1 Local Reel Mount Electrical and Mechanical Control
- 1 Sealed Continuous Contact Collector Assembly
- 1 Removable Drip Pan for Cleaning

2 19" (MINIMUM) FLATSCREEN COLOR INDUSTRIAL TV MONITOR NTSC / PAL COLOR STANDARDS

1 PCU ASSEMBLY [RACK MOUNT]

1 CCU ASSEMBLY [RACK MOUNT]

- 1 Alpha Numeric Information Display, with Multi Paging and Defect Coding
- 1 Remote "QWERTY" Keyboard
- 1 On Screen Footage Display

1 TEST CABLE

18.7" MINI KEYBOARD

1 BRACKET, LOGITECH CONTROLLER, K2

1 WIRED USB CONTROLLER

- 1 Joystick Control for Pan and Tilt Zoom Camera to Include:
- 1 360 Degree Rotate
- 1 330 Degree Optical Pan
- 1 Joystick Control for All Steering Functions & Forward / Reverse Directions for Transporter
- 1 Camera Lift Control for Optional Electronic Camera Lift
- 1 All Other Controls for Camera to Include:
- 1 Camera Iris and Focus Override & Zoom
- 1 Camera Lights & Shutter Control for Light Enhancement
- 1 Camera Diagnostics & Auto Home
- 1 Cruise Control to Set Speed of the Transporter for Hands Off Operation
- 1 All Reel Controls to Include: Retrieve, Release, and Variable Speed [Excluding Dolly Systems]

1 WIRELESS CONTROLLER

- 1 Joystick Control for Pan and Tilt Zoom Camera to Include:
- 1 360 Degree Rotate
- 1 330 Degree Optical Pan
- 1 Joystick Control for All Steering Functions & Forward / Reverse Directions for Transporter
- 1 Camera Lift Control for Optional Electronic Camera Lift
- 1 All Other Controls for Camera to Include:
- 1 Camera Iris and Focus Override & Zoom
- 1 Camera Lights & Shutter Control for Light Enhancement
- 1 Camera Diagnostics & Auto Home
- 1 Cruise Control to Set Speed of the Transporter for Hands Off Operation
- 1 All Reel Controls to Include: Retrieve, Release, and Variable Speed [Excluding Dolly Systems]

1 [RACK MOUNT] COMPUTER W/GraniteNet BASIC TO INCLUDE (MINIMUM):

- 1 Motherboard with LGA 1151 Socket and Intel Z270 Chipset
- 1 Intel Core i7-6700K 4.0 GHz Processor
- 1 8 GB of DDR4 (Double Data Rate) 2133 RAM
- 1 USB Video Capture Device for MPEG 1 / 2 / 4 / WMV
- 1 Video Display Adapter, 2GB, HDMI, DVI, VGA
- 1 LAN, On Board Network Connections, 10 / 100 / 1000 Mbps
- 4 USB 2.0 Ports
- 4 USB 3.0 Ports
- 2 USB 3.1 Ports
- 2 RS232 Serial Comm Ports
- 1 Bluetooth v4.0
- 1 WiFi MU-MIMO 802.11 a/b/g/n/ac dual frequency band 2.4/5 GHz
- 5 On Board Audio Ports
- 1 DVD + / RW DVD Burner 20x / CD RW 40x Internal Optical Drive
- 1 1 TB (7,200 RPM) SATA Hard Drive
- 1 250 GB M.2 Solid State Drive
- 1 500 Watt 1U ATX Power Supply
- 1 Industrial Hardened Case Slim 2U Design for 19" Rack
- 1 Windows 10 Professional 64-bit Operating System
- 1 GraniteNet Basic Software

1 WIRELESS KEYBOARD AND MOUSE SET

- 1 HP OFFICEJET COLOR PRINTER
- 1 GraniteNet BASIC SUPPORT PLAN
- 1 GraniteNet OFFICE KIT

1 GraniteNet OFFICE SUPPORT PLAN

1 LACP MODULE GraniteNet SOFTWARE

1 LATERAL INSPECTION MODULE GraniteNet SOFTWARE

1 SELF PROPELLED LATERAL INSPECTION / EVALUATION SYSTEM, WHEELED, FOR 6" - 30" MAINLINE AND 3" - 8" LATERAL INSPECTION, WITH LATERAL PAN & TILT CAMERA AND PAN AND TILT / ZOOM MAINLINE CAMERA, AND WIRELESS CONTROL TO INCLUDE:

- 1 Mainline Pan, Tilt, and Zoom Camera to Include:
- 1 Mainline Solid State Color Sewer TV Camera with:
- 1 Pan, Tilt & Rotate Camera Head
- 1 40:1 Zoom Ratio, 10x Optical Zoom, 4x Digital Zoom, NTSC Color Standard
- 1 360 Degree Range of Rotation, 270 Pan Viewing Angle, Panning 360 Degrees
- 1 Auto Iris, Auto Focus, Manual Override of Focus and Iris
- 1 Camera will also be Used for:
- 1 Monitoring Lateral Pan & Tilt Camera During Extend / Retract Operation
- 1 Light Assembly, Pan & Tilt Zoom Camera, 6" 72" lines
- 1 White LED Field Replaceable Lamps
- 1 Automatic Centering
- 1 Lateral Pan & Tilt Camera to Include:
- 1 Solid State Color Sewer TV Camera with:
- 1 Continuous 360 Degree Rotation, 360 Degree Pan, and 270 Degree Tilt
- 1 Sonde, Built in, for Locating Purposes with:
- 1 Switchable Frequencies, Choice of 8kHz and 512 Hz
- 1 Purge and Pressurization Valve, for Lateral Pan & Tilt Camera
- 1 Dual Wiper System Built Into Lateral Pan & Tilt Camera
- 1 Built in Directional White LED Lighting for Lateral Pan Tilt Camera for:
- 1 3" 15" Line Illumination
- 1 Powered Built in Self Leveling Feature, Manual Focus, and Auto Exposure
- 3 Guide Probes of varying lengths for Lateral Pan & Tilt Camera
- 1 Lateral Launcher, for Lateral Pan and Tilt Camera to include:
- 1 Self Propelled Launcher Robot with Freewheel, Forward, and Power Reverse
- 1 Camera Head Mounting Assembly with Rotation Positioning, Articulating Hinge
- 1 Push Cable Drive Assembly Two-Speed Extend / Retract Camera Positioning
- 1 Rear tip-up connector
- 1 Interconnect Cable for Launcher to Push Cable
- 1 Interconnect Cable for Control System to Power Control Unit
- 1 Single-point quick wheel removal system
- 1 6 each 3.5" diameter tires for 6" pipe
- 1 6 each 4.375" diameter tires for 8" pipe
- 1 6 each 5" diameter tires for 10"-15" pipe
- 1 Pneumatic Tire Kit for 12" 15" pipe
- 1 Rear Housing Assembly to Add Optional Rear View Color Camera
- 1 Lateral Reel / Control Assembly / Wireless Controller
- 1 Electric Reel with Slipring and Clutch for:
- 1 Powered Retrieve of Push Cable
- 1 Control System to Include Launcher / Self Propelled Robot Control with:
- 1 Extend / Retract, Left / Right Rotation, Camera Selection
- 1 Picture In Picture Selection / Cable Drive Speed
- 1 1000 ft. Video Cable, 8 Conductor with Cable End Termination
- 1 Controller with Forward, Freewheel, and Power Reverse / Variable Speed Control:
- 1 Self-Propelled Launcher Robot
- 1 All Launcher, Camera, and Reel Functions Shall be Controlled by the Wireless
- Hand Held Summit System Controller
- 1 Rear- View Camera
- 1 Color NTSC Camera
- 1 Lightring with (12) Solid State White LEDs

1 QUICK CABLE LOCK PIGTAIL COUPLER KIT

- 1 120' PUSH CABLE FOR LATERAL INSPECTION SYSTEM
 1 SPARE 120' PUSH CABLE FOR LATERAL INSPECTION SYSTEM
- 1 MANHOLE TOP ROLLER ASSEMBLY, TV ONLY
- 1 MANHOLE ADAPTER CLAW HOOK
- 6 POLE ASSY, RETRIEVAL/DOWNHOLE TL, 58"
- 1 INVERT ROLLER ASSEMBLY
- 1 RETRIEVAL HOOK
- 1 MULTI CONDUCTOR TV ONLY TOOL KIT
- 1 Milliampmeter Tool
- 1 Electrical Tape
- 1 Needle Nose Pliers
- 1 Six-In-One Screwdriver
- 1 6" Adjustable Wrench
- 1 Anti Seize Grease
- 1 9-Piece Allen Wrench kit
- 1 Solder Iron Kit
- 1 Industrial Pliers
- 1 5/32 T-Handle Hex Wrench
- 1 Multi Conductor TV Only Operation Manual
- 1 Parts Catalog
- 1 Cable Repair Kit DVD
- 1 TV Only Training DVD
- 1 TRAINING, ON-SITE (THREE DAYS)
- 1 FOLLOW UP TRAINING, ON-SITE (THREE DAYS) WITHIN ONE YEAR AFTER DELIVERY
- 1 TRUCK DELIVERY-FLORIDA

"The Standard of the Industry"

CUES TV VEHICLE QUOTE

VENICE CITY OF (FL)

John Monaville VENICE, FL 34285 JMonville@Venicegov.com

Below you will find pricing on a CUES TV/LAMP2 Truck based on your request.

CUES Trucks are available for purchase using several methods including the NJPA Contract, HGAC Contract, and of course, are offered as a Sole Source purchase as well. We understand you have choices when it comes to choosing a vendor for your CCTV Equipment, we feel we are the best choice for the following reasons...

- ✓ Cues, Inc. is the leading manufacturer of CCTV video equipment in the world and has been in business for over 50 years.
- √ 100% American Made. All our Engineering, Sales, Services, and Support are completed in-house, in the USA.
- ✓ The Cues Factory, Customer Support Center, and Stock Room are all centrally located in Orlando, FL.
- ✓ We carry over \$25 million in Parts and Loaner Inventory with over 98% of them shipping the same day.
- ✓ Loaner Equipment is Available for the Lifetime that you own Cues Products...meaning limited downtime.
- ✓ The <u>only</u> manufacturer who has its own Software Support Staff and solely manufactures the Granite Software Platforms.
- ✓ No 3rd Parties. No Dealers. We provide direct factory sales, service, and support for the lifetime of the product.

CUES is the only manufacturer physically located in Florida and the only manufacturer to offer a direct factory relationship. Our customer service team is second to none and it would be an honor to earn your business. Please don't hesitate to contact me with any questions and thank you for your time and the opportunity to provide this quote.

DELIVERY ESTIMATE	PAYMENT TERMS	EXPIRATION DATE	
120 DAYS AFTER RECEIPT OF ORDER 1	NET 30 W.A.C ²	30 DAYS FROM 10/29/2018	
		PRICE	
FORD F-550 GAS — CUES TV/LAMP2 VEHICLE - PLEASE REVIEW THE FULL EQUIPMENT LIST ON TH	\$274,980.00 ³		
OPTIONAL PRICE WITH TRADE-IN OF EXISTING EN	\$260,000.00		

Sincerely,

Chris Parker

Regional Sales Manager - Florida

Cell: 407.446.7445 | cparker@cuesinc.com

¹ Delivery is an estimate based on Production and Inventory as of date of quote and are subject to change based date of order received. For accurate delivery information, please contact your CUES Representative at time of order for updated delivery terms.

³ NET 30 is based on an active and current CUES account with approved credit application on file with CUES Accounting. If you are a new customer and do not have an established CUES Account or your account has been inactive for more than 12 months full payment is due at time of order

Pricing does not include any applicable local sales tax that may be applied to your order based on your tax-exempt status.

User:

Mayes, Jon

Organization:

City of Venice, FL

Logout



My DemandStar

Buyers

Account Info

FAOs

Log Bid [View Bids]

Log Quote

View Quotes

Supplier Search

Build Broadcast List

Bid Details

Bid Information

EDIT

Agency City of Venice, FL

Bid Type Letter of Interest

Bid Number LOI-149-0-2019/JM

Fiscal Year

Bid Writer Jon Mayes

Bid Name

Notice of Intent to Award a Single/Sde Source Procurement of a F-550 truck with City specified Cues TV equipment

Bld Status

Under Evaluation

Bid Status Text

This is not a Request for Proposals and there is no solicitation available. The proposed contract action is for product or services for which the City intends to negotiate and award with only one source under the authority of and in accordance with Florida State Statute 287.057(3)(c). Any responses received as a result of this Notice of Intent shall be considered solelyfor the purpose of determining whether to conduct a competitive procurement. Responses will not be considered as a proposals bids or quality.

not be considered as proposals, blds, or quotes.

Award To

Due Date/Time 11/12/2018 2:00 PM Eastern

Broadcast Date 11/2/2018

Bld Bond

Project Estimated

\$274,980.00 Budget

Plan (blueprint)

Distribution Options Distribution Method

Download and Mail

Distributed By DemandStar

Distribution Notes None

The City of Venice, Florida intends to negotiate sole-source procurement for a F-550 truck with City specified Cues

Scope of Work TV equipment installed. The Citywould contract this progrement with Cues TV of Orlando, FL. This is an acquisition

with an estimated value of \$ 274,980.00.

E-Bldding

Legal Ad

VIEW

Please select either the View or Edit button to manage legal ad

Pre-Bid Conference

Publications

No Publications Data Found

Documents

EDIT

Bid Package sole source- Cues TV (8 Pages, Complete)

Commodity Codes

004-072-00 - TRUCKS, INCLUDING, DIESEL, GASOLINE, ELECTRIC, HYBRID, AND ALTERNATIVE FUEL

030-890-00 - WATER SUPPLY, GROUNDWATER, SEWAGE TREATMENT, AND RELATED EQUIPMENT, NOT FOR AIR CONDITIONING, STEAM BOILER, OR LABORATORY REAGENT WATER 030-890-63 - Sewer Analyzing, Monitoring, Probe and Related Equipment 030-890-64 - Sewer Inspection Equipment

Statistics

Planholders There are 2 planholders for this bid

Broadcast List 255 suppliers have been notified

Supplemental Suppliers 0 Supplemental Suppliers

Filtered No

Post-Bid Viewers 0 viewer(s)

<< Return

DemandStar is a product of DemandStar Corporation (c). All rights reserved. | Terms of Use | Privacy

User:

Mayes, Jon

Organization:

City of Venice, FL

Logout



My DemandStar

Buyers

Account Info

FAQs

Log Bid [View Bids] Log Quote

Supplier Search View Quotes

Build Broadcast List Reports

Planholders List

Member Name City of Venice, FL

Bid Number LOI-149-0-2019/JM

Bid Name

Notice of Intent to Award a Single/Sole Source Procurement of a F-550 truck with City specified Cues TV

equipment installed.

1 Document(s) found for this bid

2 Planholder(s) found.

Add Planholder

Supplier Name 🛆	Phone	Fax	Doc Count	Attributes	Programs	Actions
Purchasing Consulting LLC	8888133544		1			Documents
RR Surety	2819021029		1			Documents

Page 1 of 1

Format for Printing No V

<< Return

Export to Excel

DemandStar is a product of DemandStar Corporation (c). All rights reserved. | Terms of Use | Privacy